

SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS NO.
80/94	2626.2-R-1	COOK	452
STA.	TO STA.		7
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62113	INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
				ROADWAY	RETAINING WALLS	SURVEILLANCE	LIGHTING-INDIANA	INDIANA	BRIDGE OVER HOHMAN	BRIDGE OVER LITTLE CALUMET	BRIDGE OVER HARRISON	LIGHTING-INDIANA		
MX033303	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE MAINTENANCE	SQ M	255	14	0	0	0	251	0	0	0	0		
MX033276	TEMPORARY SOIL RETENTION SYSTEM	SQ M	328		328									
MX406078	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N105	M TON	146.9	248.2	0	0	0	498.7	0	0	0	0		
MX406220	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N105	M TON	898.2	327.9	0	0	0	570.3	0	0	0	0		
MX512010	TEMPORARY SHEET PILING (TO REMAIN IN PLACE)	SQ M	2161.4		2161.4			0	0	0	0	0		
MX704012	TEMPORARY CONCRETE BARRIER (INSTALL ONLY)	METER	4463	1573	0	0	0	2890	0	0	0	0		
MZ013825	PROTECTIVE SHIELD	SQ M	176.3						135	548	117			
MZ013825	CONTROLLED LOW-STRENGTH MATERIAL	CU M	176.3	176.3	0	0	0	0	0	0	0	0		
MZ022800	FENCE REMOVAL	METER	495	429	0	0	0	66	0	0	0	0		
X0301229	ACCIDENT INVESTIGATION SITE	CAL MD	7	7	0	0	0	0	0	0	0	0		
X0322463	CONNECTION TO EXISTING SEWER	EACH	9	9										
X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	672	371	0	0	0	301	0	0	0	0		
X0323879	SERVICE PATROL	CAL DA	716	630	0	0	0	86	0	0	0	0		
X0324045	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE REMOVAL	EACH	1	1	0	0	0	0	0	0	0	0		
X4210390	LUG SYSTEM COMPLETE (SPECIAL)	EACH	1	1	0	0	0	0	0	0	0	0		
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	.4	0	0	0	.6	0	0	0	0		
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	240	96	0	0	0	144	0	0	0	0		
X7015000	CHANGEABLE MESSAGE SIGN	CAL MD	15	6	0	0	0	9	0	0	0	0		
XX001443	STEEL PLATES TO BE INSTALLED ON DRAINAGE STRUCTURE	EACH	40	17	0	0	0	23	0	0	0	0		
XX002424	CONNECTION TO EXISTING STRUCTURE	EACH	14	7	0	0	7	0	0	0	0	0		
Z0002605	BAR SPLICERS, SPECIAL	EACH	36	36	0	0	0	0	0	0	0	0		
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	.4	0	0	0	.6	0	0	0	0		
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	12	0	0	0	0	12	0	0	0	0		
Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1	0	0	0	0	0	0	0	0		
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 2	EACH	2	0	0	0	0	2	0	0	0	0		
M2130361	EXPLORATION TRENCH 3.1 METER DEPTH	METER	144	144	0	0	0	0	0	0	0	0		
X0324687	NOISE ABATEMENT WALL ANCHOR ROD ASSEMBLY	EACH	326	0	121	0	0	155	0	50	0	0		
MX033407	CONDUIT EMBEDDED IN STRUCTURE, 50MM DIAMETER CNC	METER	548	0	0	548	0	0	0	0	0	0		
MX030510	CONDUIT ATTACHED TO STRUCTURE, 100MM DIA., PVC, SCHEDULE 80	METER	320	0	0	0	0	0	0	0	0	320		
X0324753	INDIANA STATE LINE RADIO TOWER SITE WORK	LSUM	1	0	0	0	0	1	0	0	0	0		
X0324754	PRESENT STRUCTURE, STR. NO. I-80-1-8460, REMOVE PORTIONS (INDIANA)	L SUM	1	0	0	0	0	0	0	1	0	0		
MX030511	EXCAVATION FOUNDATION, UNCLASSIFIED (INDIANA)	CU M	10188	0	0	0	0	9310	0	878	0	0		
MX030512	EXCAVATION WET (INDIANA)	CU M	166	0	0	0	0	0	0	166	0	0		
MX030513	EXCAVATION DRY (INDIANA)	CU M	455	0	0	0	0	0	0	455	0	0		
MX030514	STRUCTURE BACKFILL (INDIANA)	CU M	153	0	0	0	0	0	0	153	0	0		

© SPT-31

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SUMMARY OF QUANTITIES

SCALE _____ DATE 07/04
DRAWN BY ACE/CAD
CHECKED BY TAE



Rev. 10-19-04

Rev.