

# SUMMARY OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	8
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62113		INDOT DES. NO. 0100987		

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	Y030-1E	1000-2A	SFTY-2A	X071-2A	SFTY-2A	Y030-1E	ROADWAY	RETAINING WALLS	SURVEIL-LANCE	LIGHTING-ILLINOIS	INDIANA	BRIDGE OVER HOHMAN	BRIDGE OVER LITTLE CALUMET	BRIDGE OVER HARRISON	LIGHTING-INDIANA
				1000-2A	Y007	Y032-1F	Y032-1E	CONSTRUCTION TYPE CODE	1000-2A	Y007	Y032-1F	Y032-1E	1000-2A	Y007	Y032-1F	Y032-1E	1000-2A	Y007
MN030515	RIPRAP, REVETMENT (INDIANA)	SQ M	2122	0	0	0	0	0	0	0	0	0	0	0	0	2122	0	0
MN030516	TEST PILE, 356mm (INDIANA)	EACH	18	0	0	0	0	0	0	0	0	0	0	11	0	7	0	0
MN030517	PILE, CONCRETE, STEEL SHELL ENCASED, 6.35mm, 356mm (INDIANA)	METER	15489.5	0	0	0	0	0	0	0	0	0	0	12624	0	2865.5	0	0
MN030518	CONCRETE, A. SUBSTRUCTURE (INDIANA)	CU M	4564.3	0	0	0	0	0	0	0	0	0	0	3661.6	0	902.7	0	0
MN030519	CONCRETE C. SUPERSTRUCTURE (INDIANA)	CU M	554.7	0	0	0	0	0	0	0	0	0	0	0	554.7	0	0	0
MN030520	REINFORCING BARS, EPOXY COATED (INDIANA)	KG	386360	0	0	0	0	0	0	0	0	0	0	251190	0	135170	0	0
X031A-756	THREADED TIE BAR ASSEMBLY, EPOXY COATED (INDIANA)	EACH	1889	0	0	0	0	0	0	0	0	0	0	0	0	1889	0	0
X031A-757	SURFACE SEAL (INDIANA)	L SUM	1	0	0	0	0	0	0	0	0	0	0	0.25	0	0.75	0	0
X031A-758	FIELD WELDED STUD SHEAR CONNECTOR (INDIANA)	EACH	10464	0	0	0	0	0	0	0	0	0	0	0	0	10464	0	0
X031A-769	ANCHOR BOLT (INDIANA)	EACH	154	0	0	0	0	0	0	0	0	0	0	0	0	154	0	0
MN030521	PIPE, UNDERDRAIN, PERF., 1.63mm, 150mm (INDIANA)	METER	580	0	0	0	0	0	0	0	0	0	0	580	0	0	0	0
MN030522	STRUCTURAL EXPANSION JOINT, SS (INDIANA)	METER	43.7	0	0	0	0	0	0	0	0	0	0	0	0	43.7	0	0
X0302-60	IMPACT ATTENUATOR, TEMPORARY (FULLY REDIRECTIVE - NARROW) TEST LEVEL 3	EACH	2	2														
X0324776	MASOURY COATING (INDIANA)	L SUM	1															
X0324777	FIELD OFFICE EQUIPMENT	CAL MO	15	7.5										7.5				

- SPECIALTY ITEMS
- • 100% STATE
- • • 100% INDIANA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
I-80/94/US 6  
KINGERY-BORMAN EXPRESSWAY  
BURNHAM ROAD TO US 41  
**SUMMARY OF QUANTITIES**

SCALE: DATE 07/04      DRAWN BY: ACE/CAD  
CHECKED BY: TAE



Rev. 10-20-04