

SCHEDULE OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62113		INDOT DES. NO. 0100987		

EPOXY PAVEMENT MARKING - LINE 100MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS

ILLINOIS				
MOT STAGE 1				
WESTBOUND				
WHITE				
6+814.722	12.40 LT	7+380.276	12.40 LT	565.60
7+380.276	12.40 LT	7+600.000	12.40 LT	219.70
7+600.000	12.40 LT	7+673.440	13.81 LT	73.50
7+673.440	13.81 LT	7+911.799	14.01 LT	238.40
7+911.799	14.01 LT	7+948.919	13.01 LT	37.10
YELLOW				
6+814.722	2.20 LT	7+380.276	2.20 LT	565.60
7+380.280	2.20 LT	7+600.000	2.20 LT	219.70
7+600.000	2.20 LT	7+673.830	3.62 LT	73.80
7+673.830	3.62 LT	7+911.430	3.82 LT	237.60
7+911.430	3.82 LT	7+951.920	2.76 LT	40.50
MOT STAGE 2				
EASTBOUND				
WHITE				
7+517.350	13.98 RT	7+550.000	13.61 RT	32.70
7+550.000	13.61 RT	7+798.490	16.76 RT	248.50
7+798.490	16.76 RT	7+858.330	16.90 RT	59.80
7+858.330	16.90 RT	7+957.440	15.79 RT	99.10
YELLOW				
7+517.580	3.18 RT	7+798.670	6.56 RT	281.10
7+798.670	6.56 RT	7+858.200	6.70 RT	59.50
7+858.200	6.70 RT	7+954.400	5.62 RT	96.20
FINAL				
WESTBOUND				
WHITE				
7+090.000	26.28 LT	7+356.270	26.28 LT	266.30
7+356.270	26.28 LT	7+947.400	18.25 LT	591.20
YELLOW				
7+090.000	16.18 LT	7+140.000	16.18 LT	50.00
7+140.000	16.18 LT	7+166.000	15.78 LT	26.00
7+166.000	15.78 LT	7+356.270	15.78 LT	190.30
7+356.270	15.78 LT	7+950.470	7.71 LT	594.30
TOTAL = 4,866.5				

EPOXY PAVEMENT MARKING - LINE 100MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS

INDIANA				
MOT STAGE 1				
WESTBOUND				
WHITE				
7+948.919	13.01 LT	8+090.539	15.53 LT	141.60
8+090.539	15.53 LT	8+154.915	16.80 LT	64.40
8+154.915	16.80 LT	8+385.629	16.80 LT	230.70
8+385.629	16.80 LT	8+582.015	18.57 LT	196.40
8+582.015	18.57 LT	9+250.000	16.80 LT	144.90
9+250.000	16.80 LT	9+377.413	14.86 LT	127.40
YELLOW				
7+951.920	2.76 LT	8+090.940	5.33 LT	139.00
8+090.940	5.33 LT	8+154.920	6.30 LT	64.00
8+154.923	6.30 LT	8+603.684	6.30 LT	448.80
8+603.684	6.30 LT	9+250.000	6.30 LT	646.30
9+250.000	6.30 LT	9+407.583	3.83 LT	157.60
RAMP A				
20+446.100	0.00 RT	20+658.060	0.00 RT	212.00

EASTBOUND

YELLOW				
8+000.000	3.80 RT	8+045.000	4.55 RT	45.00
8+045.000	4.55 RT	8+090.000	5.30 RT	45.00
8+090.000	5.30 RT	8+603.690	5.30 RT	513.70
8+603.680	5.30 RT	9+282.580	5.30 RT	678.90
9+282.580	5.30 RT	9+312.580	5.30 RT	30.00
9+312.580	5.30 RT	9+383.320	3.89 RT	70.80
WHITE				
8+000.000	14.80 RT	8+045.000	15.15 RT	45.00
8+045.000	15.15 RT	8+090.000	15.50 RT	45.00
8+090.195	15.50 RT	8+250.001	15.50 RT	159.80
8+250.000	15.50 RT	8+414.971	18.80 RT	165.00
8+414.971	18.80 RT	8+603.689	18.80 RT	188.70
8+603.688	18.80 RT	8+760.703	18.80 RT	157.00
8+760.703	18.80 RT	8+782.102	20.16 RT	21.40
9+183.430	15.50 RT	9+282.685	15.50 RT	99.30
9+282.685	15.50 RT	9+342.583	15.50 RT	59.90
9+342.583	15.50 RT	9+372.466	14.90 RT	29.90
MOT STAGE 2				
EASTBOUND				
WHITE				
7+957.440	15.79 RT	8+067.250	15.05 RT	109.80
8+067.250	15.05 RT	8+092.250	15.05 RT	25.00
8+092.250	15.05 RT	8+131.250	15.65 RT	39.00
8+131.250	15.65 RT	8+170.000	15.65 RT	38.80
8+170.000	15.65 RT	8+411.950	9.60 RT	242.00
8+411.950	9.60 RT	8+813.360	21.51 RT	401.60
9+183.390	14.70 RT	9+282.580	14.70 RT	99.20
YELLOW				
7+954.400	5.62 RT	8+067.250	4.85 RT	112.90
8+067.250	4.85 RT	8+170.000	4.85 RT	102.80
8+170.000	4.85 RT	8+411.950	1.20 LT	242.00
8+411.950	1.20 LT	8+686.100	0.62 RT	274.20
8+686.100	0.62 RT	8+834.150	3.90 RT	148.10
8+834.150	3.90 RT	9+282.580	3.90 RT	448.40
SKIP 0.6-1.8				
8+685.630	11.41 RT	8+813.360	14.64 RT	31.95
FINAL				
WESTBOUND				
WHITE				
7+947.400	18.25 LT	8+029.150	17.02 LT	81.80
8+029.150	17.02 LT	8+154.920	16.80 LT	125.80
YELLOW				
7+950.470	7.71 LT	8+028.990	6.52 LT	78.50
8+028.990	6.52 LT	8+154.920	6.30 LT	125.90
TOTAL = 7,655.3				

EPOXY PAVEMENT MARKING - LINE 125MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS

ILLINOIS				
MOT STAGE 1				
WESTBOUND				
6+814.720	9.10 LT	7+380.280	9.10 LT	141.40
6+814.720	5.80 LT	7+380.280	5.80 LT	141.40
7+380.280	9.10 LT	7+600.000	9.10 LT	54.93
7+380.280	5.80 LT	7+600.000	5.80 LT	54.93
7+600.000	9.10 LT	7+673.570	10.51 LT	18.40
7+600.000	5.80 LT	7+673.690	7.22 LT	18.43
7+673.570	10.51 LT	7+911.680	10.72 LT	59.53
7+673.690	7.22 LT	7+911.560	7.42 LT	59.48
7+911.560	7.42 LT	7+950.860	6.38 LT	9.83
7+911.680	10.72 LT	7+949.890	9.69 LT	9.55
MOT STAGE 2				
EASTBOUND				
7+517.530	9.78 RT	7+798.550	13.16 RT	70.25
7+517.550	6.48 RT	7+798.610	9.86 RT	70.28
7+798.550	13.16 RT	7+858.280	13.30 RT	14.93
7+798.610	9.86 RT	7+858.240	10.00 RT	14.90
7+858.240	10.00 RT	7+955.380	8.91 RT	24.28
7+858.280	13.30 RT	7+956.360	12.20 RT	24.53

FINAL

WESTBOUND				
7+090.000	19.53 LT	7+140.000	19.53 LT	12.50
7+090.000	22.68 LT	7+356.270	22.68 LT	66.58
7+140.000	19.53 LT	7+166.000	19.38 LT	6.50
7+166.000	19.38 LT	7+356.270	19.38 LT	47.58
7+356.270	19.38 LT	7+949.410	11.32 LT	148.30
7+356.270	22.68 LT	7+948.450	14.64 LT	148.05
TOTAL = 1,216.5				
EPOXY PAVEMENT MARKING - LINE 125MM				

INDIANA				
MOT STAGE 1				
WESTBOUND				
7+949.890	9.69 LT	8+090.770	12.23 LT	35.23
7+950.860	6.38 LT	8+091.000	8.94 LT	35.05
8+090.680	11.93 LT	8+154.920	13.20 LT	16.08
8+090.810	8.63 LT	8+154.920	9.90 LT	16.03
8+154.920	13.20 LT	8+603.700	13.20 LT	112.20
8+154.920	9.90 LT	8+603.680	9.90 LT	112.20
8+603.680	9.90 LT	9+250.000	9.90 LT	161.58
8+603.700	13.20 LT	9+250.000	13.20 LT	161.58
8+603.680	16.80 LT	8+796.940	16.80 LT	48.33
9+250.000	13.20 LT	9+381.760	11.18 LT	32.95
9+250.000	9.90 LT	9+398.910	7.58 LT	37.23
EASTBOUND				
8+058.540	7.25 RT	8+144.450	8.60 RT	21.48
8+058.540	10.64 RT	8+144.450	11.90 RT	21.48
8+144.450	8.60 RT	8+603.680	8.60 RT	114.80
8+144.450	11.90 RT	8+603.680	11.90 RT	114.80
8+414.970	15.50 RT	8+600.100	15.50 RT	46.28
8+603.690	8.60 RT	9+282.620	8.60 RT	169.73
8+603.690	11.90 RT	9+282.650	11.90 RT	169.75
8+603.690	15.50 RT	8+762.170	15.50 RT	39.63
8+762.170	15.50 RT	8+857.360	15.50 RT	23.80
9+282.620	8.60 RT	9+312.650	7.56 RT	7.50
9+312.650	7.56 RT	9+364.240	7.56 RT	12.90
9+282.690	11.90 RT	9+312.580	11.90 RT	7.48
9+312.580	11.90 RT	9+348.990	11.17 RT	9.10
MOT STAGE 2				
EASTBOUND				
7+955.380	8.91 RT	8+067.250	8.15 RT	27.98
7+956.360	12.20 RT	8+067.250	11.45 RT	27.73
8+067.250	8.15 RT	8+092.250	8.15 RT	6.25
8+067.250	11.45 RT	8+092.250	11.45 RT	6.25
8+092.250	8.15 RT	8+131.250	8.45 RT	9.75
8+092.250	11.45 RT	8+131.250	12.05 RT	9.75
8+131.250	8.45 RT	8+170.000	8.45 RT	9.70
8+131.250	12.05 RT	8+170.000	12.05 RT	9.70
8+170.090	8.45 RT	8+412.040	2.40 RT	60.50
8+170.180	12.05 RT	8+412.130	6.00 RT	60.50
8+411.950	2.40 RT	8+685.940	4.22 RT	68.50
8+411.950	6.00 RT	8+685.780	7.81 RT	68.45
8+685.780	7.81 RT	8+834.150	11.10 RT	37.10
8+685.940	4.22 RT	8+834.150	7.50 RT	37.05
8+834.150	11.10 RT	9+282.580	11.10 RT	112.10
8+834.150	7.50 RT	9+282.580	7.50 RT	112.10
FINAL				
WESTBOUND				
7+948.450	14.64 LT	8+029.100	13.42 LT	80.70
7+949.410	11.32 LT	8+029.050	10.12 LT	79.60
8+029.050	10.12 LT	8+154.920	9.90 LT	125.90
8+029.100	13.42 LT	8+154.920	13.20 LT	125.80
TOTAL = 2,602.5				

EPOXY PAVEMENT MARKING - LINE 200MM

STATION	OFFSET(m)	STATION	OFFSET(m)	METERS

INDIANA				
MOT STAGE 1				
WESTBOUND				
8+582.015	18.57 LT	8+889.381	23.04 LT	307.40
8+796.940	16.80 LT	8+993.630	16.80 LT	196.70
8+796.940	16.80 LT	8+993.560	19.59 LT	196.60
EASTBOUND				
8+862.130	15.50 RT	8+912.130	15.50 RT	50.00
8+912.130	15.50 RT	8+991.270	16.75 RT	79.10
8+912.130	15.50 RT	9+011.290	15.50 RT	99.20
9+011.290	15.50 RT	9+183.430	15.50 RT	172.10
8+991.270	16.75 RT	9+011.250	17.10 RT	20.00
9+011.250	17.10 RT	9+063.980	18.57 RT	52.80
9+063.980	18.57 RT	9+183.430	23.50 RT	119.60
MOT STAGE 2				
EASTBOUND				
8+813.360	14.64 RT	8+834.150	14.70 RT	20.80
8+834.150	14.70 RT	8+873.910	14.70 RT	39.80
8+873.910	14.70 RT	8+973.310	14.70 RT	99.40
8+973.310	14.70 RT	8+973.090	17.21 RT	99.20
8+973.090	17.21 RT	9+034.830	18.08 RT	61.70
9+034.830	18.08 RT	9+077.930	19.00 RT	43.10
9+077.930	19.00 RT	9+127.110	20.82 RT	49.20
9+127.110	20.82 RT	9+183.450	23.50 RT	56.40
TOTAL = 1,763.1				

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
SCHEDULE OF QUANTITIES

RE	
----	--