

EARTHWORK SCHEDULE OF QUANTITIES

ALL DIMENSIONS IN METERS EXCEPT PAY ITEMS AND UNLESS NOTED OTHERWISE

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80/94	2626.2-R-1	COOK	452	21
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62113		INDOT DES. NO. 0100987		

INDIANA STA. - STA.	EARTH EXCAVATION (CU M)		TOTAL SUITABLE EXCAVATION (CU M)		EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE 15%) (CU M)		EMBANKMENT (CU M)		EARTHWORK BALANCE WASTE (-) OR SHORTAGE (+) (CU M)	
	STAGE 1	STAGE 2	STAGE 1	STAGE 2	STAGE 1	STAGE 2	STAGE 1	STAGE 2	STAGE 1	STAGE 2
	7+950 - 7+975	3.13	0.00	3.13	0.00	2.66	0.00	104.50	0.00	-101.84
7+975 - 8+000	1.50	0.00	1.50	0.00	1.28	0.00	149.25	0.00	-147.98	0.00
8+000 - 8+025	5.13	0.00	5.13	0.00	4.36	0.00	189.25	0.00	-184.89	0.00
8+025 - 8+050	19.38	0.00	19.38	0.00	16.47	0.00	188.38	0.00	-171.91	0.00
8+050 - 8+075	0.00	0.00	0.00	0.00	0.00	0.00	204.88	0.00	-204.88	0.00
8+075 - 8+100	0.00	0.00	0.00	0.00	0.00	0.00	237.25	0.00	-237.25	0.00
8+100 - 8+125	0.00	0.00	0.00	0.00	0.00	0.00	248.50	0.00	-248.50	0.00
8+125 - 8+150	0.00	0.00	0.00	0.00	0.00	0.00	265.50	0.00	-265.50	0.00
8+150 - 8+175	0.00	0.00	0.00	0.00	0.00	0.00	274.38	0.00	-274.38	0.00
8+175 - 8+200	0.00	0.00	0.00	0.00	0.00	0.00	135.25	0.00	-135.25	0.00
8+200 - 8+225	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+225 - 8+250	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+250 - 8+275	0.00	4.63	0.00	4.63	0.00	3.93	0.00	127.25	0.00	-123.32
8+275 - 8+300	0.00	38.00	0.00	38.00	0.00	32.30	0.00	230.50	0.00	-198.20
8+300 - 8+325	0.00	78.00	0.00	78.00	0.00	66.30	0.00	165.63	0.00	-99.33
8+325 - 8+350	0.00	86.75	0.00	86.75	0.00	73.74	0.00	105.63	0.00	-31.89
8+350 - 8+375	0.00	96.38	0.00	96.38	0.00	81.92	0.00	67.75	0.00	14.17
8+375 - 8+400	0.00	97.13	0.00	97.13	0.00	82.56	0.00	56.25	0.00	26.31
8+400 - 8+425	0.00	98.50	0.00	98.50	0.00	83.73	0.00	31.75	0.00	51.98
8+425 - 8+450	0.00	55.63	0.00	55.63	0.00	47.28	0.00	0.00	0.00	47.28
8+450 - 8+475	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+475 - 8+500	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+500 - 8+525	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+525 - 8+550	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+550 - 8+575	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+575 - 8+600	0.00	36.00	0.00	36.00	0.00	30.60	0.00	0.00	0.00	30.60
8+600 - 8+625	0.00	65.00	0.00	65.00	0.00	55.25	0.00	26.00	0.00	29.25
8+625 - 8+650	0.00	51.25	0.00	51.25	0.00	43.56	0.00	52.13	0.00	-8.56
8+650 - 8+675	0.00	39.75	0.00	39.75	0.00	33.79	0.00	45.75	0.00	-11.96
8+675 - 8+700	0.00	37.63	0.00	37.63	0.00	31.98	0.00	40.25	0.00	-8.27
8+700 - 8+725	0.00	43.25	0.00	43.25	0.00	36.76	0.00	41.63	0.00	-4.86
8+725 - 8+750	0.00	23.13	0.00	23.13	0.00	19.66	0.00	21.00	0.00	-1.34
8+750 - 8+775	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+775 - 8+800	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+800 - 8+825	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+825 - 8+850	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+850 - 8+875	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+875 - 8+900	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+900 - 8+925	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+925 - 8+950	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+950 - 8+975	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
8+975 - 9+000	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+000 - 9+025	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+025 - 9+050	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+050 - 9+075	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
9+075 - 9+100	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
I-80/94/US 6
KINGERY-BORMAN EXPRESSWAY
BURNHAM ROAD TO US 41
EARTHWORK SCHEDULE OF QUANTITIES

SCALE _____ DRAWN BY ACE/CAD
DATE 07/04 CHECKED BY TAE

AMERICAN
CONSULTING ENGINEERS