



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 18, 2016

SUBJECT: FAU 9722 (Washington Street)  
Section 13-00128-00-BT (Carbondale)  
Jackson County  
Contract No. 99517  
Item 104  
March 4, 2016 Letting  
Addendum (A)

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

### **1. Revised page 5 of the Special Provisions.**

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Maureen M. Addis, P.E.  
Acting Bureau Chief of Design and Environment

A handwritten signature in black ink, reading "Ted B. Walschleger P.E." with a stylized flourish at the end.

By: Ted B. Walschleger, P.E.  
Engineer of Project Management

## **Portland Cement Concrete Sidewalk**

This item of work shall consist of the construction of a Portland Cement Concrete Sidewalk of the width specified on a 4" aggregate base at locations shown on the Plans and as directed by the Engineer. This work shall be per Section 424 of the Standard Specifications and as shown in the Plans.

All sidewalk and driveway construction shall meet the United States Access Board's Public Rights-of-Way Accessibility Guidelines (PROWAG) published July 26, 2011.

Curing of this walk shall be done for the time specified in the Standard Specifications by either using the correct membrane curing compound or white polyethylene sheeting. During winter months and with the approval of the Engineer, clear or black polyethylene sheeting may be used for cold weather protection.

Curb ramps with detectable warnings shall be placed on walking surfaces at all intersections of sidewalks and streets unless otherwise noted. Curb ramps shall be constructed per the Highway Standards included in the Plans. Adjacent to the curb, a toe wall will be constructed. This wall shall be 6 inches thick and extend to the bottom of the curb. Reinforcement bars (#4 bars) shall extend from the toe wall longitudinally along the walk a distance of 5 feet. These bars shall be spaced 8 inches on center. No additional payment shall be made for any variation in thickness, reinforcement bars, or the toe walls.

Payment for this work shall be at the contract unit price per SQUARE FOOT for PORTLAND CEMENT CONCRETE SIDEWALK of the thickness specified and no additional compensation will be allowed. The cost of furnishing, placing, and compacting the aggregate base shall be included in the cost of PORTLAND CEMENT CONCRETE SIDEWALK of the thickness specified.

## **Detectable Warnings**

The work covered by this Specification shall conform to Section 424 of the aforesaid Standard Specifications. Detectable Warnings shall consist of a surface of truncated domes meeting the requirements of the ADAAG and the details as shown on the plans. All detectable warnings shall be cast in concrete, truncated dome tactile warning panels, red in color as manufactured by CASTinTACT (or equivalent as approved by Engineer); to conform to IDOT standard #424001 and ADA requirements.

Payment for this work shall be at the contract unit price per SQUARE FOOT for DETECTABLE WARNING.

## **Aggregate Surface Course**

This item of work shall consist of furnishing and placing one or more courses of crushed aggregate upon a prepared subgrade at the locations shown on the plans and as directed by the Engineer. The material shall be IDOT gradation CA-10. The sub-grade shall be prepared according to applicable portions of Section 301 of the Standard Specifications. The material shall be deposited and spread according to Article 402.07 of the Standard Specifications except a