SUMMARY OF QUANTITIES

URBAN 100% STATE

CONSTRUCTION TYPE CODE: SFTY-2A

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOC. 1 SN 016-1029	LOC. 2 SN 016-1030	LOC. 3 SN 016-2448	LOC. 4 SN 016-2449	LOC. 5 SN 016-2450	LOC. 6 SN 016-2451	LOC. 7 SN 016-2452	LOC. 8 SN 016-2453
50102400	CONCRETE REMOVAL	CU YD	2.9							2.9	
50300225	CONCRETE STRUCTURES	CU YD	3							3	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1060							1060	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5
67100100	MOBILIZATION	L SUM	1	0.13	0.13	0.13	0.13	0.13	0.13	0.13	0.09
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	162							162	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	3163	124	125	178	206	1182	134	1018	196
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1							1	
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1							1	
Z0073400	TEMPORARY SUPPORT SYSTEM	EACH	8					2		6	
X5080600	MECHANICAL SPLICERS	EACH	12							12	

Rev.

FILE NAME = c:\pw_work\pwidot\estimablek\d0161538\D181309-sht-plan.dgn	USER NAME = estimablek	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/5/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2009-069 BR	COOK	39	3
		CONTRACT NO. 60H77		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

D181309-sht-plan.dgn 1/5/2010 2:14:15 PM User=estimablek