

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SFTY-2A	SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		LOC 1 016-0316	LOC 2 016-0320						CODE NO	ITEM		UNIT				
X5080600	MECHANICAL SPLICERS	EACH	268	268														
50102400	CONCRETE REMOVAL	CU YD	30.5	30.5														
50157300	PROTECTIVE SHIELD	SQ YD	155	155														
50300255	CONCRETE SUPERSTRUCTURE	CU YD	30.5	30.5														
50300260	BRIDGE DECK GROOVING	SQ YD	48	48														
50300300	PROTECTIVE COAT	SQ YD	104.5	104.5														
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	20620	20620														
50500505	STUD SHEAR CONNECTORS	EACH	392	392														
50501110	STRUCTURAL STEEL REMOVAL	POUND	18830	18830														
50501130	STRUCTURAL STEEL REPAIR	POUND	660		660													
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6460	6460														
50900905	REMOVING AND RE-ERECTING EXISTING RAILING	FOOT	74	74														
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	3	1													
67100100	MOBILIZATION	L SUM	1	0.75	0.25													
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1														
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.5	0.5													
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1														
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	613	613														
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400														
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	610	610														
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	85	85														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	290	290														
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	77.1	25.7													
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1														
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2060	2060														
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1														
Z0003600	BEAM STRAIGHTENING	L SUM	1	0.75	0.25													
Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	3	3														
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1	1														

*Specialty Items