SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	300	300					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35	35					
25200110	SODDING, SALT TOLERANT	SQ YD	35	35					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45	45					
40600300	AGGREGATE (PRIME COAT)	TON	220	220					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	85	85					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2255	2255					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	235	235					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	55	55					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4600	4600					
42001300	PROTECTIVE COAT	SQ YD	50	50					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	5	5					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	50	50					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	54650	54650					
44000600	SIDEWALK REMOVAL	SQ FT	50	50					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200					
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	305	305					
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	3000	3000					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	120	120					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	75	75					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	100	100					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SQ YD	1000	1000					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SQ YD	625	625					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SQ YD	850	850					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	1380	1380					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1					

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE ROADWAY 1000					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9250	9250					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	230	230					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	59400	59400					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	600	600					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1210	1210					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	150	150					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3100	3100					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	230	230					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	59400	59400					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	600	600					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1210	1210					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	150	150					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	620	620					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	500	500					
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	25	25					
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	5	5					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	20	20					

* SPECIALTY ITEMS

Rev.

FILE NAME = c:\pw_work\PWIDOT\KELLERS\d0146123\D183409-sht-plan.dgn	USER NAME = kellers	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	MAIN STREET (ILLINOIS ST. TO IL ROUTE 83) SUMMARY OF QUANTITIES	F.A.U. RTE. 3587	SECTION C-RS-7	COUNTY COOK	TOTAL SHEETS 22	SHEET NO. 3
	PLOT SCALE = 50.0000 ' / IN.	DRAWN -	REVISED -					CONTRACT NO. 60H94		
	PLOT DATE = 12/16/2009	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT
		DATE -	REVISED -							