

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	208	208
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	50	50
25200110	SODDING, SALT TOLERANT	SQ YD	50	50
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	5	5
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	10	10
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	38	38
40600300	AGGREGATE (PRIME COAT)	TON	1,812	1,812
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	6	6
40600535	LEVELING BINDER (HAND METHOD), N70	TON	5	5
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	460	460
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	80	80
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1	1
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,810	3,810
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	10	10
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	45,300	45,300
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	15	15
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	300	300
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	440	440
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	290	290
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	60	60
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	30	30
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	510	510
55039700	STORM SEWERS TO BE CLEANED	FOOT	700	700
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	1	1
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5

• DENOTES SPECIALTY ITEM

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITY	CONSTRUCTION TYPE CODE
CODE NO.	DESCRIPTION	UNIT		ROADWAY 1000-2A
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7,190	7,190
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,100	1,100
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	30,792	30,792
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,500	4,500
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1,350	1,350
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1,050	1,050
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5,700	5,700
• 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	350	350
• 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	31,700	31,700
• 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,500	1,500
• 78000600	THERMOPLASTIC PAVEMENT-MARKING - LINE 12"	FOOT	450	450
• 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	350	350
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	310	310
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	295	295
• 88600600	DETECTOR LOOP REPLACEMENT	FOOT	240	240
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,800	1,800
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1

FILE NAME = N:\PROJ\33869\33869_30\Design\ProposedPlan\33869_30-03-Quantities.dgn



Ciorba Group, Inc.
CONSULTING ENGINEERS
5507 North Cumberland Avenue, Suite 402
Chicago, Illinois 60656
Tel. 773.775.4009 Fax 773.775.4014

USER NAME = alou	DESIGNED - AL	REVISED -
	DRAWN - AL	REVISED -
PLOT SCALE = 1:8000' / 1"	CHECKED - WBL	REVISED -
PLOT DATE = 12/15/2009	DATE - 12/11/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL 126
US 30 (LOCKPORT STREET) TO I-55
SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.U. RTE. 0323	SECTION 121 RS-1	COUNTY WILL	TOTAL SHEETS 19	SHEET NO. 3
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60H98	