

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000-2A					CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	URBAN 1000-2A				
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	32	32					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	32	32					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6863	6863				
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	32	32					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2143.5	2143.5				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	2125	2125					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	52000	52000				
25200110	SODDING, SALT TOLERANT	SO YD	2125	2125					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	18500	18500				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	94	94					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	875	875				
40600300	AGGREGATE (PRIME COAT)	TON	468	468					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	6500	6500				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	176	176					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1100	1100				
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4826	4826					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2143.5	2143.5				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	52000	52000				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	775	775					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	18500	18500				
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	11464	11464					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	875	875				
42001300	PROTECTIVE COAT	SO YD	1551	1551					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6500	6500				
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH, SPECIAL	SO YD	1000	1000					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1100	1100				
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SO FT	4500	4500					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1326	1326				
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	116977	116977					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1300	1300				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	1000	1000					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	4181	4181				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3000	3000					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	205.6	205.6				
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	423	423					* X8950200	REBUILD EXISTING HANDHOLE	EACH	7	7				
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	3438	3438					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	7	7				
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	1052	1052					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	2106	2106													
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1													
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	45	45													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	160	160													
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	52	52													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4													
67100100	MOBILIZATION	L SUM	1	1													
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1													

* SPECIALTY ITEMS