

SUMMARY OF QUANTITIES

90% FED./10% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	SFTY-3J GUARDRAIL
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	48	48
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,694	2,694
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	675	675
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	57	57
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
63200310	GUARDRAIL REMOVAL	FOOT	3,128	3,128
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701432	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
78200405	GUARDRAIL MARKERS	EACH	7	7
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	57	57
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	514	514
X0325917	TURF ESTABLISHMENT	SQ YD	1,974	1,974
NP X2503100	MOWING	UNIT	196	196

* DENOTES SPECIALTY ITEM
NP= Non participating

Rev. 2-23-10

FILE NAME =	USER NAME = .USER.	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL IMPROVEMENTS - NORTHERN WILL COUNTY SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#	PLOT SCALE = 50,0000' / IN.	DRAWN -	REVISED -			•	2009-090GRR	WILL	17	3
	PLOT DATE = 12/17/2009	CHECKED -	REVISED -			• VARIOUS				CONTRACT NO. 60143
		DATE -	REVISED -							ILLINOIS FED. AID PROJECT
					SCALE: NTS	SHEET NO. 1 OF 1 SHEETS		STA.	TO STA.	