

SUMMARY OF QUANTITIES

90% FED.
10% STATE

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	SFTY-3U ROADWAY
20200100	EARTH EXCAVATION	CU YD	336	336
20400800	FURNISHED EXCAVATION	CU YD	420	420
21400100	GRADING AND SHAPING DITCHES	FOOT	1,750	1,750
28000305	TEMPORARY DITCH CHECKS	FOOT	180	180
28000400	PERIMETER EROSION BARRIER	FOOT	1,085	1,085
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	129	129
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	2,177	2,177
50102400	CONCRETE REMOVAL	CU YD	1	1
50300225	CONCRETE STRUCTURES	CU YD	20	20
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	760	760
50800105	REINFORCEMENT BARS	POUND	1,900	1,900
54002020	EXPANSION BOLTS 3/4 INCH	EACH	40	40
NP 55039700	STORM SEWERS TO BE CLEANED	FOOT	160	160
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	913	913
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	26	26
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	7	7
63200310	GUARDRAIL REMOVAL	FOOT	1,786	1,786
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
78200405	GUARDRAIL MARKERS	EACH	10	10
78201000	TERMINAL MARKER-DIRECT APPLIED	EACH	26	26
X0325917	TURF ESTABLISHMENT	SQ YD	3,594	3,594
NP X2503100	MOWING	UNIT	323	323
70100315	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	EACH	1	1
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1
X0322250	TEMPORARY INFORMATION SIGNING	SQ FT	308	308

* Specialty Items
NP = Non-participating

FILE NAME =	USER NAME = .USER.	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GUARDRAIL IMPROVEMENTS - EASTERN WILL COUNTY SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN - EF	REVISED -			2009-092 GRR	WILL	18	3	
PLOT SCALE = 50,0000' / IN.		CHECKED - RS	REVISED -			CONTRACT NO. 60145				
PLOT DATE = 12/17/2009		DATE - 11/13/2009	REVISED -			ILLINOIS FED. AID PROJECT				
					SCALE: NTS	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.		

Rev.