

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	20	20					63200310	GUARDRAIL REMOVAL	FOOT	150	150					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	5	5					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
20400800	FURNISHED EXCAVATION	CU YD	12	12					67100100	MOBILIZATION	L SUM	1	1					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	325	325					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
25000210	SEEDING, CLASS 2A	ACRE	0.005	0.005					70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1	1					70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1	1					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1	1					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	16200	16200					
25200110	SODDING, SALT TOLERANT	SO YD	300	300					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1500	1500					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	82	82					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	44000	44000					
40600300	AGGREGATE (PRIME COAT)	TON	405	405					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4000	4000					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	152	152					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1200	1200					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	4175	4175					70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	400	400					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	5500	5500					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	600	600					*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	1500	1500					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	9915	9915					*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	44000	44000					
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	16	16					*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	4000	4000					
42001300	PROTECTIVE COAT	SO YD	550	550					*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1200	1200					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	10	10					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	100	100					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1550	1550					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	101200	101200					*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3					
44000600	SIDEWALK REMOVAL	SO FT	100	100					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1300	1300					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000					*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1603	1603					
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	3150	3150					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52					
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	500	500					44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	150	150					
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	850	850					Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SO YD	140	140					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	85	85					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	60	60					
55039700	STORM SEWERS TO BE CLEANED	FOOT	2000	2000					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	1	1														
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	30	30														
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	3	3														
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	53	53														
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	3														

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	US 12 /IL RTE. 59 (IL RTE. 59 TO EAST ST.) SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cdpw_work\KIDOT\KELLERS\00158556\0104910-sh-plandgn	DRAWN -	REVISED -	334			(106-2 & 117) RS-1	LAKE	27	3	
PLOT SCALE = 500000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60150							
PLOT DATE = 12/18/2009	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT							

Rev.