SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1550	1550					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	238	238					
40600300	AGGREGATE (PRIME COAT)	TON	1190	1190					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	446	446					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	787	787					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	225	225					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	9820	9820					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7667	7667					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21128	21128					
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	278,731	278,731					
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	803	803					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	523	523					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	112	112					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	27	27					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	11,089	11,089					
50102400	CONCRETE REMOVAL	CU YD	5.2	5.2					
50200100	STRUCTURE EXCAVATION	CU YD	9	9					
50800105	REINFORCEMENT BARS	POUND	2000	2000					
54003000	CONCRETE BOX CULVERTS	CU YD	5.2	5.2					
63301215	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	82	82					
64200105	SHOULDER RUMBLE STRIP	FOOT	140,293	140,293					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	68754	68754					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	146,693	146,693					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	763	763					
* 81018500	CONDUIT PUSHED, 2" DIA. GALVANIZED STEEL	FOOT	625	625					
* 81400200	HEAVY DUTY HANDHOLE	EACH	8	8					
* X8850102	INDUCTION LOOP	FOOT	540	540					
* X0326872	CONDUIT IN TRENCH, 2" DIA. HIGH DENSITY POLYETHYLENE, COILABLE	FOOT	200	200					
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	200	200					

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000					
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	7800	7800					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3478	3478					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	135	135					
* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	17,536	17,536					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,758	1,758					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,406	1,406					
X0322729	MATERIAL TRANSFER DEVICE	TON	50,988	50,988					
X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2					
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	15.8	15.8					
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1					
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	319200	319200					
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	270	270					
X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	FOOT	15600	15600					
X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	38300	38300					
40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	27,868	27,868					
X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	23,120	23,120					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	872	872					
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	50	50					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	400	400					
~~70400200~~	~~RELOCATE TEMPORARY CONCRETE BARRIER~~	~~FOOT~~	~~260~~	~~260~~					
~~Z0030270~~	~~IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3~~	~~EACH~~	~~1~~	~~1~~					
~~Z0030330~~	~~IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3~~	~~EACH~~	~~1~~	~~1~~					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	225	225					
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	32	32					
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2					

*SPECIALTY ITEMS

Rev. Rev. 2-10-10

FILE NAME = c:\pw_work\pwidot\abebawd\d0169692\stf-plandgn	USER NAME = abebawd	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/23/2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	) (1&2) RS-11	WILL	45	3
		CONTRACT NO. 60153		

FED. ROAD DI | . NO. 1 | ILLINOIS | FED. AID PROJECT