

SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY				
				I000									I000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	1550	1550					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	7800	7800				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	238	238					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3478	3478				
40600300	AGGREGATE (PRIME COAT)	TON	1190	1190					* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	135	135				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	446	446					* 78004220	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"	FOOT	17,536	17,536				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,758	1,758				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	787	787					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1,406	1,406				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	225	225					X0322729	MATERIAL TRANSFER DEVICE	TON	50,988	50,988				
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	9820	9820					X0324685	TEST STRIP (STONE MATRIX ASPHALT)	EACH	2	2				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	7667	7667					X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	15.8	15.8				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	21128	21128					X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1				
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	278,731	278,731					X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	319200	319200				
44002220	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5"	SQ YD	803	803					X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	270	270				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	523	523					X0325876	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 8 INCH	FOOT	15600	15600				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	112	112					X0326107	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 5 INCH	FOOT	38300	38300				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	27	27					40603153	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, STONE MATRIX ASPHALT, N80	TON	27,868	27,868				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	11,089	11,089					X4066685	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, STONE MATRIX ASPHALT, N80	TON	23,120	23,120				
50102400	CONCRETE REMOVAL	CU YD	5.2	5.2					40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	872	872				
50200100	STRUCTURE EXCAVATION	CU YD	9	9					X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
50800105	REINFORCEMENT BARS	POUND	2000	2000					X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	50	50				
54003000	CONCRETE BOX CULVERTS	CU YD	5.2	5.2					70400100	TEMPORARY CONCRETE BARRIER	FOOT	260	260				
63301215	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	82	82					70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	260	260				
64200105	SHOULDER RUMBLE STRIP	FOOT	140,293	140,293					Z0030270	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, WIDE), TEST LEVEL 3	EACH	1	1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1				
67100100	MOBILIZATION	L SUM	1	1													
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	20	20													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	68754	68754													
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	146,693	146,693													
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	763	763													

*SPECIALTY ITEMS

Rev.

FILE NAME =	USER NAME = abebawa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
c:\pwworking\abebawa\d0169692\stt-plan.dgn		DRAWN -	REVISED -									55	(1&2) RS-11	WILL	45	3			
PLOT SCALE = 50.0000 1/ IN.		CHECKED -	REVISED -									SCALE: SHEET NO. OF SHEETS STA. TO STA.				FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			
PLOT DATE = 12/23/2009		DATE -	REVISED -													CONTRACT NO. 60153			