



- ① PROP. HOT-MIX ASPHALT SURFACE REMOVAL, 4"  
PROP. POLYMERIZED HMA SURFACE COURSE, SMA, N80, 2"  
PROP. POLYMERIZED HMA BINDER COURSE, SMA, N80, 2"
- ② PROP. HOT-MIX ASPHALT SURFACE REMOVAL, 4"  
PROP. HMA SURFACE COURSE, MIX. 'D', N70, 1 1/2"  
PROP. HMA BINDER COURSE, IL-19, N70, 2 1/2"
- ③ PROP. HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"  
PROP. HMA SURFACE COURSE, MIX. 'D', N70, 1 1/2"  
PROP. POLY. LEVELING BINDER, IL-4.75, N50, 3/4"
- A PROP. PREFORMED PLASTIC PAVEMENT MARKING, TYPE B-INLAID-LINE 5" (TYP.)
- B PROP. THERMOPLASTIC PAVEMENT MARKING-LINE 4", WHITE (TYP.)
- C PROP. THERMOPLASTIC PAVEMENT MARKING-LINE 4", YELLOW (TYP.)
- D PROP. THERMOPLASTIC PAVEMENT MARKING-LINE 8", WHITE (TYP.)
- E PROP. THERMOPLASTIC PAVEMENT MARKING-LINE 12", WHITE (TYP.)

FILE NAME =	USER NAME = abebawa	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL. ROUTE 55 GRUNDY COUNTY LINE TO KANKAKEE RIVER</b>			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw_work\VPWIDOT\ABEBAWA\00159692\sh-	1an.dgn	DRAWN -	REVISED -		55	99 (1&2) RS-11	WILL	45	11			
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.			CONTRACT NO. 60153				
PLOT DATE = 12/23/2009	DATE -	REVISED -	REVISED -		ILLINOIS FED. AID PROJECT							