

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 100%-STATE	TRAFFIC Y031-IF 100%-STATE	ALSIP Y031-3D 100% VILLAGE				CODE NO		ITEM	UNIT	ROADWAY 1000-2A 100% STATE	TRAFFIC Y031-IF 100% STATE	ALSIP Y031-3D 100% VILLAGE		
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	250	250					
40600300	AGGREGATE (PRIME COAT)	TON	55	55					72000100	SIGN PANEL - TYPE 1	SQ FT	70		70				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	21	21					72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	49.5		49.5				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	181.5	181.5					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	104	104					78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2849	2849					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	123	123					78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	815	815					
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1347	1347					78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	120	120					
42001300	PROTECTIVE COAT	SQ YD	16	16					78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	204	204					
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	12493	12493					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	131	131					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	50	50					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	105	105					
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	549	549					81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	747		747				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	220	220					81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	119		119				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	220	220					81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	119		119				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	109	109					81000900	CONDUIT IN TRENCH, 3 1/2" DIA., GALVANIZED STEEL	FOOT	102		102				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2					81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	20		20				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	5					81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	390		390				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	10		10				
67100100	MOBILIZATION	L SUM	1	1					81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	361		361				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					81100800	CONDUIT ATTACHED TO STRUCTURE, 3" DIA., GALVANIZED STEEL	FOOT	32		32				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					81100900	CONDUIT ATTACHED TO STRUCTURE, 3 1/2" DIA., GALVANIZED STEEL	FOOT	37		37				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2247	2247					81400100	HANDHOLE	EACH	9		9				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	181.5	181.5					81400200	HEAVY-DUTY HANDHOLE	EACH	4		4				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2849	2849					81400300	DOUBLE HANDHOLE	EACH	2		2				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	815	815					81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1075		1075				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	120	120					85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1		1				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	204	204					87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1292		1292				

*Specialty Items