

SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN 90% FED. 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		ROADWAY 1000-2A 100% STATE	TRAFFIC Y031-IF 100% STATE	ALSIP Y031-3D 100% VILLAGE	CODE NO	ITEM	UNIT		ROADWAY 1000-2A 100% STATE	TRAFFIC Y031-IF 100% STATE	ALSIP Y031-3D 100% VILLAGE
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	6040	6040		* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT		862	862		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	3034	3034		* X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT		1292	1292		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	38	38		21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD		9	9		
87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL 14 FT.	EACH	2	2		25200110	SODDING, SALT TOLERANT	SQ YD		9	9		
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	1	1		* 87700230	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH		1	1		
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1	1		* X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH		6	6		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	2	2		* X8809045	COMBINATION SIGNAL HEAD, LED, 2-FACE, 1-3 SECTION OPTICALLY PROGRAMMED, BRACKET MOUNTED	EACH		2	2		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8	8									
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4	4									
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	46	46									
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	6	6									
88030210	SIGNAL HEAD, LED, 2-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2	2									
88200210	TRAFFIC SIGNAL BACKPLATE, LOUVERED, ALUMINUM	EACH	12	12									
88500100	INDUCTIVE LOOP DETECTOR	EACH	8	8									
88600100	DETECTOR LOOP, TYPE I	FOOT	488	488									
88700200	LIGHT DETECTOR	EACH	4		4								
88700300	LIGHT DETECTOR AMPLIFIER	EACH	1		1								
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1	1									
89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	8103	8103									
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	1									
89502380	REMOVE EXISTING HANDHOLE	EACH	16	16									
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	7	7									
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	102.8									
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1									
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	567	567									
X6060500	CORRUGATED MEDIAN REMOVAL	SQ FT	654	654									
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	1									
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	1									

*Specialty Items