

SUMMARY OF QUANTITIES

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY 100% STATE	1000-2A STATE
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26
40600300	AGGREGATE (PRIME COAT)	TON	131	131
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	49	49
40600895	CONSTRUCTING TEST STRIP	EACH	2	2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1,103	1,103
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL-BUTT JOINT	SQ YD	355	355
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	324	324
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2,749	2,749
42101300	PROTECTIVE COAT	SQ YD	850	850
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	30,009	30,009
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1,037	1,037
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	1,448	1,448
44003100	MEDIAN REMOVAL	SQ FT	4,540	4,540
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	750	750
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	305	305
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	215	215
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,336	1,336
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	687	687
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	7	7
60260100	INLETS TO BE ADJUSTED	EACH	1	1
60624600	CORRUGATED MEDIAN	SQ FT	4,540	4,540
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6
67100100	MOBILIZATION	L SUM	1	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1

* DENOTES SPECIALTY ITEM

PAY ITEM NUMBER	DESCRIPTION	UNIT	URBAN TOTAL QUANTITY 100% STATE	1000-2A STATE
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3,294	3,294
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,019	1,019
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	32,943	32,943
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	4,617	4,617
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3,428	3,428
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	533	533
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	510	510
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16,472	16,472
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2,309	2,309
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,714	1,714
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	482	482
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	291	291
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	291	291
81400215	HEAVY DUTY HANDHOLE TO BE ADJUSTED	EACH	2	2
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1,765	1,765
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	257	257
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	953	953
X4421000	PARTIAL DEPTH PATCHING	TON	75	75
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	445	445
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1,833	1,833
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3

* DENOTES SPECIALTY ITEM

P:\jcb2009\200903023-06\cadd\stata.dgn\08\01E2548-4ht-SDD.dgn

FILE NAME =	USER NAME = .USER.	DESIGNED - EF	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GREENWOOD AVE. - GOLF ROAD (IL 58) TO WEST LAKE AVE. SUMMARY OF QUANTITIES	F.A.U. RTE. 2743	SECTION 1316 RS-2	COUNTY COOK	TOTAL SHEETS 25	SHEET NO. 3		
	PLOT SCALE = 50.0045' / IN.	CHECKED - RS	REVISED -			SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT		
	PLOT DATE = 12/2/2009	DATE - 12/02/09	REVISED -									