

TREE ACTIVITIES / CLEARING SCHEDULE

STATION	SIDE	TREE REMOVAL UNITS	TEMP. FENCE FOOT	TREE PRUNING EACH	TREE ROOT PRUNING EACH	MULCH SQ YD
0+00 - 5+00	LT	0	100	1	1	0
	RT	12, 14	0	0	0	0
5+00 - 10+00	LT	10, 12	200	2	2	93
	RT	10	300	2	2	0
10+00 - 15+00	LT	0	0	0	0	0
	RT	0	0	0	0	0
15+00 - 20+00	LT	0	0	1	1	0
	RT	0	0	1	1	0
20+00 - 22+47	LT	0	0	0	0	0
	RT	0	0	1	1	0
50+00 - 52+34	LT	0	0	0	0	0
	RT	0	0	0	0	0
100+00 - 104+70	LT	0	0	0	0	0
	RT	0	0	0	0	0
TOTAL		58	600	8	8	93

PAVEMENT SCHEDULE

STATION	SIDE	HMA SURFACE REMOVAL VARIABLE DEPTH SQ YD	GEOTECHNICAL FABRIC SQ YD	AGGREGATE BASE COURSE, TYPE B 6" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE, MIX C TON
0+00 - 5+00	LT	528	999	878	1.08	121
	RT					
5+00 - 10+00	LT	106	920	804	0.98	121
	RT					
10+00 - 15+00	LT	622	992	873	1.08	121
	RT					
15+00 - 20+00	LT	337	1,051	921	1.13	121
	RT					
20+00 - 22+47	LT	-	399	343	0.41	60.3
	RT					
50+00 - 52+34	LT	291	449	388	0.47	50.9
	RT					
100+00 - 104+70	LT	518	830	721	0.87	112.8
	RT					
TOTAL		2,402	5,639	4,928	6.01	708

FENCE AND SITE FURNISHINGS

STATION	SIDE	FENCE LF	BENCH INSTALLATION EACH
0+00 - 5+00	LT	0	0
	RT	0	0
5+00 - 10+00	LT	77	0
	RT	0	0
10+00 - 15+00	LT	44	0
	RT	0	0
15+00 - 20+00	LT	0	0
	RT	0	1
20+00 - 22+47	LT	0	0
	RT	0	0
50+00 - 52+34	LT	0	0
	RT	0	0
100+00 - 104+70	LT	0	0
	RT	0	0
TOTAL		121	1

SEEDING SCHEDULE

STATION	SIDE	LAWN SEEDING SF
0+00 - 5+00	LT	2,334
	RT	3,276
5+00 - 10+00	LT	3,482
	RT	2,640
10+00 - 15+00	LT	2,982
	RT	3,084
15+00 - 20+00	LT	3,709
	RT	2,928
20+00 - 22+47	LT	1,410
	RT	1,533
50+00 - 52+34	LT	1,489
	RT	1,396
100+00 - 104+70	LT	2,832
	RT	2,861
TOTAL		35,956

PAVEMENT MARKING SCHEDULE

Station	THERMOPLASTIC PAVEMENT MARKING - LINE 4" Solid Yellow LF	THERMOPLASTIC PAVEMENT MARKING - LINE 4" Solid White LF	THERMOPLASTIC PAVEMENT MARKING - LINE 4" 12'-3" Yellow Skip LF	THERMOPLASTIC PAVEMENT MARKING - LINE 12" Solid White LF	THERMOPLASTIC PAVEMENT MARKING - LINE 24" Solid White LF
0+00 - 1+00	100	200	-	30	12
1+00 - 1+84	-	168	15	-	-
1+84 - 2+84	100	287	-	30	12
3+36 - 4+36	100	200	-	30	12
4+36 - 9+00	-	930	93	-	-
9+00 - 12+00	-	616	60	-	-
12+00 - 17+75	-	1151	115	-	-
17+75 - 18+75	100	290	-	30	12
19+30 - 21+58	228	455	-	60	24
22+13 - 22+47	34	87	-	-	-
50+00 - 51+00	100	200	-	30	12
51+00 - 51+94	-	188	6	-	-
51+94 - 52+34	-	SEE 103+50 - 104+64	8	-	-
100+00 - 103+50	-	700	15	-	-
103+50 - 104+64	40	268	45	-	-
TOTAL	802	5740	357	210	84

Intersection	THERMOPLASTIC PAVEMENT MARKING - LINE 12" Solid White LF	THERMOPLASTIC PAVEMENT MARKING - LINE 24" Solid White LF
Marquette Drive and Cornell Avenue	444	74
Marquette Drive Mid-block (Sta. 11+25.00)	168	0
Marquette Drive at Richards Drive (Sta. 19+00.00)	444	60
Marquette Drive at Richards Drive (Sta. 21+88.00)	168	60
TOTAL	1224	194

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
CHICAGO PARK DISTRICT - JACKSON PARK
MARQUETTE DRIVE BICYCLE PATH

SCALE: 1" = 20'
DATE: 10/16/2009
DRAWN BY: MJP
CHECKED BY: TB