

SUMMARY OF QUANTITIES

#	Coded Pay Item Number	Pay Item	Unit	ESTIMATED QUANTITIES	CONSTRUCTION TYPE CODE		
					Y047	Y007	Y031-IF
* 1	A2007116	TREE, QUERCUS RUBRA (RED OAK), 2" CALIPER, BALL AND BURLAPPED	EACH	7	7		
* 2	A2006516	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2" CALIPER, BALL AND BURLAPPED	EACH	7	7		
* 3	A2005616	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2" CALIPER, BALL AND BURLAPPED	EACH	7	7		
* 4	A2002916	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2" CALIPER, BALL AND BURLAPPED	EACH	7	7		
* 5	A2002716	TREE, CARYA OVATA (SHAGBARK HICKORY), 2" CALIPER, BALL AND BURLAPPED	EACH	7	7		
6	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	417	417		
7	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	175	175		
8	20101200	TREE ROOT PRUNING	EACH	375	375		
9	20101100	TREE TRUNK PROTECTION	EACH	375	375		
10	20200100	EARTH EXCAVATION	CU YD	5,840	5,840		
11	20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	60	60		
12	20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	60	60		
13	21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	16,690	16,690		
* 14	21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	13,310	13,310		
* 15	21101645	TOPSOIL FURNISH AND PLACE, 12"	SQ YD	190	190		
* 16	25000200	SEEDING, CLASS 2	ACRE	1.25	1.25		
* 17	25000210	SEEDING, CLASS 2A	ACRE	0.25	0.25		
* 18	25000312	SEEDING, CLASS 4A	ACRE	1.25	1.25		
* 19	25000350	SEEDING, CLASS 7	ACRE	2.75	2.75		
* 20	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	250	250		
* 21	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	250	250		
* 22	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	250	250		
* 23	25100115	MULCH, METHOD 2	ACRE	2.75	2.75		
* 24	25100630	EROSION CONTROL BLANKET	SQ YD	13,310	13,310		
* 25	25100900	TURF REINFORCEMENT MAT	SQ YD	570	570		
26	25200200	SUPPLEMENTAL WATERING	UNIT	22	22		
* 27	28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	275	275		
28	28000305	TEMPORARY DITCH CHECKS	FOOT	560	560		
29	28000400	PERIMETER EROSION BARRIER	FOOT	11,350	11,350		
30	28000510	INLET FILTERS	EACH	11	11		
31	31101400	SUB-BASE GRANULAR MATERIAL, TYPE B, 6"	SQ YD	175	175		
32	35100400	AGGREGATE BASE COURSE, TYPE A, 5"	SQ YD	16,525	16,525		
33	42001300	PROTECTIVE COAT	SQ YD	175	175		
34	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,550	1,550		
35	42400800	DETECTABLE WARNINGS	SQ FT	196	196		
36	44000100	PAVEMENT REMOVAL	SQ YD	20	20		
37	44000600	SIDEWALK REMOVAL	SQ FT	1,000	1,000		
38	44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100		
39	50901760	PIPE HANDRAIL	FOOT	450	450		
40	50901765	PIPE HANDRAIL, SPECIAL	FOOT	348	348		

* INDICATES SPECIALTY ITEM

#	Coded Pay Item Number	Pay Item	Unit	ESTIMATED QUANTITIES	CONSTRUCTION TYPE CODE		
					Y047	Y007	Y031-IF
41	60250200	CATCH BASINS TO BE ADJUSTED	EACH	1	1		
42	60250500	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1		
43	60255500	MANHOLES TO BE ADJUSTED	EACH	2	2		
44	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	7	7		
45	67100100	MOBILIZATION	L SUM	1	1		
46	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
47	72000100	SIGN PANEL - TYPE 1	SQ FT	102	102		
48	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	208	208		
49	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	40	40		
* 50	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50	50		
* 51	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	50	50		
* 52	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	700	700		
* 53	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	70	70		
54	78300100	PAVEMENT MARKING REMOVAL	SQ FT	140	140		
* 55	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	5			5
* 56	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	21			21
* 57	81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5			5
* 58	85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1			1
* 59	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	184			184
* 60	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	196			196
* 61	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	2			2
* 62	87502490	TRAFFIC SIGNAL POST, GALVANIZED STEEL 15 FT.	EACH	4			4
* 63	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	8			8
* 64	87900200	DRILL EXISTING HANDHOLE	EACH	2			2
* 65	88102717	PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	2			2
* 66	88600100	DETECTOR LOOP, TYPE I	FOOT	59			59
* 67	88800100	PEDESTRIAN PUSH-BUTTON	EACH	2			2
* 68	89502200	MODIFY EXISTING CONTROLLER	EACH	1			1
69	X0301852	DEWATERING STRUCTURE NO. 1	EACH	3	3		
70	X0320139	TEMPORARY CONSTRUCTION FENCE	FOOT	15,550	15,550		
71	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	103	103		
72	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	625	625		
73	X0325789	INTERPRETIVE SIGNAGE COMPLETE	EACH	5	5		
74	X0350810	BOLLARD REMOVAL	EACH	18	18		
75	X0350805	FOLD DOWN BOLLARDS	EACH	10	10		
76	X0426200	DEWATERING	L SUM	1	1		
77	X0974300	SIGN REMOVAL	EACH	8	8		
78	X4023000	TEMPORARY ACCESS (ROAD)	EACH	8	8		
79	XX000503	SPLIT RAIL FENCE	FOOT	120	120		
80	XX000613	MODULAR BLOCK RETAINING WALL	SQ FT	1,125	1,125		

* INDICATES SPECIALTY ITEM