ORIGINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

FINAL SURVEY		BY	DATE
	SURVEYED		
	PLOTTED		
NOTE BOOK	TEMPLATE		
	AREAS		
NO.	AREAS CHECKED		

..\ALT00$OA.DGN, ..\IP000$RL.DGN, ..\RDW00$RS.DGN, ..\ROW00$RA.DGN, ..\DRA00$OK.DGN, ..\SCR00$X9.DGN, ..\RDW00$XA.DGN, ..\ROW00$RB.DGN, ..\UTL00$RN.DGN, ..\UTL00$RN.DGN, ..\UTL00$RNORIGINAL.DGN, ..\XSC00$XB_WETLANDS.DGN
8-4-2009, 5:05:29 T:\DOCUMENT\93I0003\CIVIL\DGN\XSC00$X1.DGN STANKRJ

NOTE: THE EXCACT LOCATION AND ELEVATION OF EXISTING STRUCTURES, UTILITIES, AND PIPING SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR.

79+00.00

℄ WALKUP RD

STAGE I

EX ROW

927.76 928.14 1:21.2 927.69 EX ROW 2% 927.49 1:50 PR ROW

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 16.16
EMBANKMENT= 0.19
UNS MTL (TOPSOIL EXC)= 12.32

78+00.00

℄ WALKUP RD

STAGE I

EX ROW

927.71 928.09 1:11 927.10 2% EX ROW 926.90 1:3 P/E

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 4.58
EMBANKMENT= 2.38
UNS MTL (TOPSOIL EXC)= 12.62

77+00.00

℄ WALKUP RD

STAGE I

EX ROW

927.32 927.70 1:6.4 926.30 2% 926.10 EX ROW 1:6

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 12.33
EMBANKMENT= 2.18
UNS MTL (TOPSOIL EXC)= 12.11

76+10.00

℄ WALKUP RD

STAGE I

EX ROW

926.87 927.25 1:4 925.73 2% 925.53 EX ROW P/E 1:3

76+00.00

℄ WALKUP RD

STAGE I

EX ROW

926.81 927.19 1:3.8 925.70 2% 925.50 EX ROW P/E 1:3

ALL UNITS IN SQ FT STAGE I
EARTH EXCAVATION= 3.20
EMBANKMENT= 45.88
UNS MTL (TOPSOIL EXC)= 14.37

PROPOSED CROSS-SECTIONS: WALKUP ROAD

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9008B5	00-00246-01-FP	MCHENRY	236	192
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT		STA. TO STA.		
CONTRACT NO: 63266				