F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
80085	00-00246-01-FP	MCHENRY	236	203
STA.	TO STA.			
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 63266

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK		
TYPICALS/ AREAS		
NO.	AREAS CHECKED	

..\ALTOD#A.DGN, ..\TP00D#S.DGN, ..\RDWD0#S.DGN, ..\RDWD0#R.DGN, ..\UTLDD#N.DGN, ..\UTLDD#NORIGINAL.DGN, ..\VXSCD0#X8_WETLANDS.DGN, ..\VROWDD#R3.DGN, ..\SUPROD_5R.DGN

SCALE: 1" = 10'

58 59 60 61 62 63

PROPOSED CROSS-SECTIONS: WALKUP ROAD

NOTE: THE EXCACT LOCATION AND ELEVATION OF EXISTING STRUCTURES, UTILITIES, AND PIPING SHALL BE VERIFIED IN THE FIELD BY THE CONTRACTOR.

112+00.00

ALL UNITS IN SQ.FT STAGE 1
EARTH EXCAVATION= 3.95
EMBANKMENT= 28.54
UNS. MTL.(TOPSOIL EXC)= 18.06

113+00.00

ALL UNITS IN SQ.FT STAGE 1
EARTH EXCAVATION= 0.00
EMBANKMENT= 62.27
UNS MTL (TOPSOIL EXC)= 15.85
UNS MTL (UNDERCUT) = 2.25

113+03.14

RESIDENTIAL HMA ENTRANCE

ALL UNITS IN SQ.FT STAGE 1
EARTH EXCAVATION= 0.91
EMBANKMENT= 36.81
UNS MTL.(TOPSOIL EXC)= 13.23

114+00.00

ALL UNITS IN SQ.FT STAGE 1
EARTH EXCAVATION= 1.49
EMBANKMENT= 23.72
UNS MTL.(TOPSOIL EXC)= 12.32

115+00.00

℄ WALKUP RD
STAGE 1
EX ROW
PR ROW
EX DRIVE
1:3
2%
12.95
855.39
855.15
855.02
854.64
850.69
850.71
850.58
850.38
850.51
850.82
850.70
847.73
848.11
847.36
847.16
845.47
845.85
845.11
844.91