

SPECIALTY ITEMS	SPECIAL PROVISION	PAY ITEM #	PAY ITEM	UNIT	SOUTH LOT QUANTITY	NORTH LOT QUANTITY	COMPASS LOT QUANTITY	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
									ROADWAY I00-2A	LIGHTING Y030-1E
		20200100	EARTH EXCAVATION	CU YD	1,202	1,073	4,687	6,962		6,962
		20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	121	108	469	698		698
	*	20700420	POROUS GRANULAR EMABANKMENT, SUBGRADE	CU YD	121	108	469	698		698
		20800150	TRENCH BACKFILL	CU YD	19	7	633	659		659
		21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	265	288	1,329	1,882		1,882
	*	25200850	SODDING, SALT TOLERANT (SPECIAL)	SQ YD	798	898	2,998	4,694		4,694
	o	25300700	TRANSPLANTED SALVAGED SHRUBS	EACH	25	25	0	50		50
		28000400	PERIMETER EROSION BARRIER	FOOT	833	779	1,818	3,430		3,430
		28000500	INLET AND PIPE PROTECTION	EACH	7	4	17	28		28
	*	28101400	RIPRAP	SQ YD	36	0	0	36		36
		28200200	FILTER FABRIC	SQ YD	36	0	0	36		36
		35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	1,929	2,371	2,736	7,036		7,036
		35501300	HOT-MIX ASPHALT BASE COURSE, 4"	SQ YD	1,929	2,371	2,736	7,036		7,036
		40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	675	830	958	2,463		2,463
		40600300	AGGREGATE (PRIME COAT)	TON	5	6	7	18		18
		40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	270	332	384	986		986
		40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	163	200	230	593		593
		42000100	PORTLAND CEMENT CONCRETE PAVEMENT 6"	SQ YD	0	0	45	45		45
	*	42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	551	228	3,025	3,804		3,804
		44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	373	77	133	583		583
		44000600	SIDEWALK REMOVAL	SQ FT	596	0	451	1,047		1,047
	*	44004400	PAVEMENT REMOVAL (SPECIAL)	SQ YD	0	0	148	148		148
		55000640	STORM SEWERS, CLASS A, TYPE 3, 12"	FOOT	0	0	197	197		197
		60100085	GEOTECHNICAL FABRIC FOR FRENCH DRAINS	SQ YD	0	0	437	437		437
	*	60202710	CATCH BASINS, TYPE A, 4' DIAMETER, WITH SPECIAL FRAME AND GRATE	EACH	0	0	4	4		4
	*	60209510	CATCH BASINS, TYPE C, WITH SPECIAL FRAME AND GRATE	EACH	0	0	5	5		5
	*	60208700	INLETS, TYPE A, WITH SPECIAL FRAME AND GRATE	EACH	1	1	2	2		2
	*	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	2	2	3	7		7
	*	60604200	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (SPECIAL)	FOOT	1,111	1,102	3,486	5,699		5,699
	*	66411900	TEMPORARY FENCE	FOOT	833	779	1,621	3,233		3,233
		67100100	MOBILIZATION	L SUM	0	0	0	1		1
		70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	0	0	0	1		1
		72000100	SIGN PANEL - TYPE 1	SQ FT	31.75	6.25	6.25	44		44
	*	72400900	REMOVE SIGN PANEL	EACH	1	0	0	1		1
		72900100	METAL POST - TYPE A	FOOT	36	33	174	243		243
	o	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	953	986	5,343	7,282		7,282
	o	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	0	0	0	59		59
	o	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	27	18	12	55		55
	o	78300405	THERMOPLASTIC PAVEMENT MARKING REMOVAL	FOOT	330	0	0	330		330
	o	81000400	CONDUIT IN TRENCH, 1 1/4" DIA., GALVANIZED STEEL	FOOT	0	0	2,000	2,000		2,000
	o	81400100	HANDHOLE	EACH	0	0	23	23		23
	o	83600100	LIGHT POLE FOUNDATION	EACH	0	1	22	23		23
	o	A2002920	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	7	11		11
	o	A2004616	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	3	5		5
	o	A2005420	TREE, LIRIODENDRON TULIPIFERA (TULIP TREE), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	4	6		6
	o	A2006520	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	13	17		17
	o	A2007120	TREE, QUERCUS RUBRA (RED OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	4	6		6
	o	A2007620	TREE, TAXODIUM DISTICHUM (COMMON BALD CYPRESS), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2	9	13		13
	o	A2007820	TREE, TILIA AMERICANA (AMERICAN LINDEN/ BASSWOOD), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	3	5		5
	o	A2C056G3	TREE, QUERCUS MACROCARPA (BURR OAK), CONTAINER GROWN, 3 GALLON	EACH	1	1	3	5		5
	o	C2C11026	SHRUB, SYRINGA PATULA MISS KIM (MISS KIM MANCHURIAN LILAC), 30" HEIGHT, 5-GALLON CONTAINER	EACH	25	25	0	50		50
	*	X0321309	CONCRETE PAD	SQ YD	0	0	20	20		20
	o	84200806	REMOVAL OF POLE FOUNDATION, CONCRETE	EACH	0	1	0	0		1
	*	X0322671	STABILIZED CONSTRUCTION ENTRANCE	SQ YD	251	134	167	552		552
	*	X0322917	PROPOSED STORM SEWER CONNECTION TO EXISTING MANHOLE	EACH	1	1	2	4		4
	o	X0323857	EXISTING LIGHT POLE FOUNDATION ADJUSTMENT	EACH	2	0	0	2		2
	o	X0324182	ELECTRICAL CABLE IN CONDUIT, TRIPLEX NO. 6, 2-1C AND NO. 8, 1-1C	FOOT	0	0	2,176	2,176		2,176
	o	X2110104	TOPSOIL FURNISH AND PLACE, 4" (SPECIAL)	SQ YD	798	898	2,955	4,651		4,651
	*	40600982	HOT-MIX ASPHALT SURFACE REMOVAL - CURB JOINT	SQ YD	342	54	89	485		485
	*	XX001249	ORNAMENTAL FENCE	FOOT	0	46	0	46		46
	o	A2008453	TREE ULMUS ACCOLADE (HYBRID ELM) 3" CALIPER, BALLED AND BURLAPPED	EACH	2	2	9	13		13
	*	XX005690	STORM SEWER, DUCTILE IRON PIPE, CLASS 5212"	FOOT	68	29	0	97		97
	o	XX006834	ELECTRICAL CONNECTION TO EXISTING LIGHTING SYSTEM	EACH	0	0	1	1		1
	*	42400800	DETECTABLE WARNINGS	SQ FT	6	0	12	18		18
	*	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	0	0	0	1		1
	o	XX008327	AERIAL MOUNTED PARKING STALL NUMBER SIGNS	EACH	0	0	86	86		86
	*	XX008328	AGGREGATE BASE COURSE, TYPE B, CA7, 6"	SQ YD	0	0	4,442	4,442		4,442
	*	XX008329	AGGREGATE BASE COURSE, TYPE B, CA7, 8"	SQ YD	0	0	3,958	3,958		3,958
	*	XX008330	BIOSWALE	SQ YD	0	0	1,386	1,386		1,386
	*	XX008331	FARE COLLECTION MACHINE	EACH	0	0	2	2		2
	*	XX008332	FARE COLLECTION MACHINE SHELTER	L SUM	0	0	1	1		1
	o	XX008333	GROUND MOUNTED PARKING STALL NUMBER SIGNS	EACH	32	33	105	170		170
	*	XX008334	HANDICAP STALL RESTRIPING AND SIGNAGE	EACH	4	0	4	4		4
	*	2800510	INLET FILTERS	EACH	7	4	17	28		28
	*	XX008335	PERVIOUS ASPHALT, 4"	SQ YD	0	0	3,958	3,958		3,958
	*	XX008336	PERVIOUS CONCRETE, 8"	SQ YD	0	0	4,442	4,442		4,442
	o	XX008065	LIGHTING UNIT COMPLETE	EACH	0	0	22	22		22
	*	61139900	STORM SEWERS, SPECIAL 6"	FOOT	0	0	765	765		765

PLANS PREPARED BY: 	SURVEY - DJG	DESIGNED - DJG	REVISED - 10/05/09 PER BLRS	VILLAGE OF GLENVIEW PROJECT E 08-56	SUMMARY OF QUANTITIES	F.A. RT.:	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	UTILITIES - JC	DRAWN - DJG	REVISED -			NA	08-00169-00-PK	COOK	24	3	
	CHECKED - DJG	CHECKED - LVA	REVISED -			SCALE: NONE SHEET NO. 3 OF 24 SHEETS		CONTRACT NO. 63360		ILLINOIS FED. AID PROJECT	
	DATE - 04-23-09	DATE - 09-17-09	REVISED -								