

F.A.U. ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET No.
2783	09-00247-00-RS	COOK	27	2
PLAN NOTES, HIGHWAY STANDARDS AND DETAILS				
FED. ROAD DIST. No. 1	ILLINOIS	CONTRACT NO. 63397		

**GENERAL NOTES**

1. THE CONTRACTOR SHALL CALL J.U.L.I.E. AT 800-892-0123 OR 811
2. ANY REFERENCE TO STANDARDS THROUGHOUT THE PLANS AND SPECIAL PROVISIONS SHALL BE INTERPRETED TO BE THE LAST STANDARDS OF THE ILLINOIS DEPARTMENTS OF TRANSPORTATION AND THE VILLAGE OF OAK PARK.
3. THE LOCATION AND ELEVATION OF THE VARIOUS UNDERGROUND UTILITIES AS SHOWN ON THE PLANS ARE APPROXIMATE. THE CONTRACTOR SHALL COORDINATE VARIOUS CONSTRUCTION ACTIVITIES WITH UTILITY COMPANIES.
4. ELEVATIONS ARE BASED ON CITY OF CHICAGO DATUM 1929 ADJUSTMENT, WHERE 0.00 C.C.D. = 579.48 FEET ABOVE MEAN SEA LEVEL.
5. BENCH MARKS ON OLD FIRE HYDRANTS: TOP OF THE 1" BOLT AFTER ARROW HEAD. BENCH MARKS ON NEWER 4-BOLT HYDRANTS: TOP OF THE NORTH-EAST OR TAGGED BOLT.
6. THE CONTRACTOR SHALL MAINTAIN POSITIVE DRAINAGE DURING THE CONSTRUCTION.
7. THE CONTRACTOR TO PROTECT ALL EXISTING PLANTS AND TREES FOR WHICH THE CONTRACT DOES NOT PROVIDE REMOVAL. THE PROTECTION OF PLANT AND TREES AND THE REPAIR OR REPLACEMENT SHALL BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF STANDARD SPECIFICATIONS.
8. SIDEWALK RAMPS ACCESSIBLE TO THE DISABLED SHALL BE PROVIDED AT ALL CROSSWALKS, DRIVEWAYS, AND ALLEYS.
9. THE CONTRACTOR TO MAINTAIN PEDESTRIAN AND VEHICULAR ACCESS TO ALL PRIVATE AND COMMERCIAL PROPERTIES DURING THE CONSTRUCTION. IF NECESSARY, THE CONTRACTOR TO NOTIFY THE ENGINEER ABOUT SCHEDULED DRIVEWAYS REMOVAL MINIMUM 6 DAYS IN ADVANCE.
10. THE CONTRACTOR TO CONTACT THE VILLAGE OF OAK PARK FOR A WATER METER.
11. ACTUAL LOCATION AND SIZE OF BASE PATCHES WILL BE DETERMINED IN THE FIELD. NO COMPENSATION WILL BE ALLOWED FOR NOT USED PATCHING QUANTITIES.
12. ALL SURFACE AND FULL DEPTH PAVEMENT SAWCUTTING SHALL BE CONSIDERED INCLUDED IN THE COST OF REMOVAL ITEMS.
13. THE CONTRACTOR TO NOTIFY ENGINEER OF ANY ABNORMAL, UNSOUND, AND/OR DETORIORATED CONDITIONS OF PAVEMENT BASES, PIPES AND STRUCTURES WHICH ARE NOT SCHEDULED FOR REMOVAL/REPAIR.
14. NO SEWER WORK IS ALLOWED PRIOR TO ISSUANCE OF MWRD PERMIT.
15. UNLESS OTHERWISE DIRECTED, ALL EXISTING DRAIN TILES ENCOUNTERED AND NOT SHOWN ON THE PLANS SHALL BE RECONNECTED.
16. SEWER TRENCHES SHALL BE TEMPORARY BACKFILLED AT THE END OF WORKING DAY. SECURED STEEL PLATE IS ALLOWED ONLY WITH APPROVAL OF THE ENGINEER.
17. ALL RADII ON ALLEY RETURNS SHALL BE OF 8 FEET, AND ALL RADII ON LOCAL STREET INTERSECTION CORNERS SHALL BE OF 15 FEET, UNLESS OTHERWISE INDICATED.
18. THE CONTRACTOR TO PROTECT NEWLY INSTALLED PAVEMENTS. ANY PAVEMENT DAMAGED OR VANDALISED DURING CURING SHALL BE REMOVED AND REPLACED WITH NO ADDITIONAL COMPANSATION.
19. CALCULATION RATES FOR SELECTED ITEMS:  
 BITUM MATERIAL PRIME COAT  
 0.07 GAL/SQYD FOR ASPHALT, BRICK, PCC BASES  
 0.30 GAL/SQYD FOR AGGREGATE BASES  
 HMA MIXES 112 LBS/SQYD/INCH

HIGHWAY STANDARDS

- 000001-05 STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
- 424001-05 CURB RAMPS FOR SIDEWALKS
- 442201-03 CLASS C AND D PATCHES
- 602001-01 CATCH BASIN TYPE A
- 602301-02 INLET TYPE A
- 602401-02 MANHOLE TYPE A
- 602501-01 VALVE VAULT TYPE A
- 604001-03 FRAME AND LID TYPE I
- 606001-04 CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
- 701501-05 URBAN LANE CLOSURE 2L 2W UNDIVIDED
- 701606-06 URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
- 701701-06 URBAN LANE CLOSURE, MULTILANE INTERSECTION
- 701801-04 LANE CLOSURE MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE
- 701901-01 TRAFFIC CONTROL DEVICES
- 886001-01 DETECTOR LOOP INSTALLATION
- 780001-02 TYPICAL PAVEMENT MARKINGS

DISTRICT ONE DETAILS

- TS-05 STANDARD TRAFFIC SIGNAL DESIGN SHEET 18
- TS-07 DETECTOR LOOP INSTALLATION SHEET 19
- BD-8 FRAMES AND LIDS ADJUSTMENT WITH MILLING SHEET 20
- BD-22 PAVT PATCHING FOR HMA SURFACED PAVEMENT SHEET 21
- BD-24 CURB AND CURB AND GUTTER REMOVAL AND REPL SHEET 22
- BD-32 BUTT JOINT AND HMA TAPER SHEET 23
- BD-33 HMA TAPER AT EDGE OF PCC PAVEMENT SHEET 24
- TC-10 TRAFFIC CTRL AND PROTECTION FOR SIDE ROADS SHEET 25
- TC-13 TYPICAL PAVEMENT MARKINGS SHEET 26
- TC-16 PAVT MARKINGS LETTERS AND SYMBOLS FOR TRAFFIC STAGING SHEET 27
- TC-21 TYPICAL MARKING FOR CLOSING STATE HIGHWAY SHEET 28

VILLAGE OF OAK PARK DETAILS, SHEET 29

- VOP-P1 CONTINUOUS PAVING OPERATION THROUGH INTERSECTION
- VOP-C2 TYPICAL SIDEWALK RAMP - PAY ITEMS LIMITS

REVISIONS:	
Oct 24, 2009	RB
Dec 2, 2009	RB
Dec 16, 2009	RB

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.U. ROUTE 2783 - RIDGELAND AVENUE  
  
 PLAN NOTES, HIGHWAY STANDARDS AND DISTRICT DETAILS  
  
 SCALE: 1"=20' (24X36)  
 HALF SIZE (11X17)  
 DATE: 9/10/09  
 DRAWN BY: RB  
 CHECKED BY: JB