

SUMMARY OF QUANTITIES

CODE NO.	DESCRIPTION	UNIT	Y030-1E QUANTITY
21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	500
21301048	EXPLORATION TRENCH 48" DEPTH	FOOT	20
25000210	SEEDING, CLASS 2A	ACRE	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	LB	9
25000500	PHOSPHORUS FERTILIZER NUTRIENT	LB	9
25000600	POTASSIUM FERTILIZER NUTRIENT	LB	9
25100630	EROSION CONTROL BLANKET	SQ YD	500
* 42400200	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	SQ FT	325
* 44000600	SIDEWALK REMOVAL	SQ FT	325
* 44201785	CLASS D PATCHES, TYPE 1, 12 INCH	SQ YD	15
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	70
81018600	CONDUIT PUSHED, 2 1/2" DIA. GALV. STEEL	FOOT	75
81018900	CONDUIT PUSHED, 4" DIA. GALV. STEEL	FOOT	380
81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	5
81702400	ELECTRIC CABLE IN CONDUIT, 600V, (XLP-TYPE USE) 3-1/C NO. 2	FOOT	85
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	60
82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	26
82500350	LIGHTING CONTROLLER, BASE MOUNT, 100AMP-240 VOLT	EACH	1
83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	26
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	260
83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	26
X8210405	LUMINAIRE SHIELD	EACH	3
XX006937	GROUND ROD, 5/8" X 10 FT.	EACH	26
81603104	UNIT DUCT, 600 V, 1/4" HDPE, WITH 4/C #6 & 1/C #6 GND XLP TYPE USE,	FOOT	5040

* SPECIALTY ITEMS

CHRISTOPHER B. BURKE ENGINEERING, LTD.
9575 W. Higgins Road, Suite 600
Rosemont, Illinois 60018
(847) 823-0500

FILE NAME =	USER NAME = ADERICCO	DESIGNED <i>AJD</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL RT. 83 AND PLAINFIELD ROAD INTERSECTION LIGHTING SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
N:\WILLOWBROOK\290244\Mech\090244_Summary.tld		DRAWN <i>KWB</i>	REVISED -			0344	09-00020-00-LT	DUPAGE	8	2	
		CHECKED <i>AJD</i>	REVISED -			SCALE: N.T.S. SHEET NO. 2 OF 6 SHEETS STA. TO STA.					
		DATE <i>11-17-2009</i>	REVISED -			CONTRACT NO. 63402					
						FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					