

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE		
				ROADWAY 1000-1A	TRAFFIC SIGNALS Y031-1F	NON-PARTICIPATING
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	2	-	2	-
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLTION	EACH	1	-	1	-
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	6,590	-	6,590	-
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1	-	1	-
* 89502380	REMOVE EXISTING HANDHOLE	EACH	3	-	3	-
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9	-	9	-
Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	885	885	-	-
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	-	-
Δ Z0076600	TRAINEES	HOUR	500	500	-	-
* XX002192	RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, COMPLETE	EACH	1	-	1	-
XX006464	DOMESTIC WATER SERVICE BOX TO BE ADJUSTED (SPECIAL)	EACH	1	1	-	-
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	104	104	-	-
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2,618	-	2,618	-
X0324450	SEGMENTAL CONCRETE BLOCK WALL, SPECIAL	SQ FT	350	350	-	-
* X0323797	PAINT NEW TRAFFIC SIGNAL POST	EACH	5	-	-	5
* X0324232	PAINT NEW MAST ARM POLE, UNDER 40 FEET	EACH	3	-	-	3
* X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	-	1	-
* X0325890	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1	EACH	1	-	1	-
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	8	8	-	-
X40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	493	493	-	-
X4420450	CLASS D PATCHES, TYPE I, 4 INCH	SQ YD	54	54	-	-
X4420452	CLASS D PATCHES, TYPE II, 4 INCH	SQ YD	80	80	-	-
X4420454	CLASS D PATCHES, TYPE III, 4 INCH	SQ YD	133	133	-	-
X4420456	CLASS D PATCHES, TYPE IV, 4 INCH	SQ YD	266	266	-	-
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1	-	1	-
* X8140074	GROUNDING EXISTING HANDHOLE FRAME AND COVER	EACH	3	-	3	-
* X8620020	UNINTERRUPTIBLE POWER SUPPLY	EACH	1	-	1	-
* X8710020	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F	FOOT	2,618	-	2,618	-
* X8730027	ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	FOOT	460	-	460	-
* X8730250	ELECTRIC CABLE IN CONDUIT, NO. 20 3/C, TWISTED, SHIELDED	FOOT	200	-	200	-

* INDICATES SPECIALTY ITEM Δ = Y080

* F.A.P. ROUTE 0305 U.S. ROUTE 14 (NORTHWEST HIGHWAY)
F.A.U. ROUTE 3877 EAST MAIN STREET

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 LICENSE NO. 184 00121 - EXPIRES 4/30/2011
 12/27/2009 10:38:23 AM



DESIGNED - JJF	REVISED - MCDPD REVIEW 11/3/09
DRAWN - CJC	REVISED - IDOT REVIEW 11/17/09
CHECKED - RWL	REVISED -
DATE - 09/11/09	FILE - 080298-500.sh+

VILLAGE CARY, ILLINOIS
U.S. ROUTE 14 AT EAST MAIN STREET RIGHT-TURN LANE STP
AND EAST MAIN STREET ARRA IMPROVEMENTS

SUMMARY OF QUANTITIES

SCALE: _____ STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	08-00054-00-CH	McHENRY	56	8
C-91-619-09			CONTRACT NO. 63404	
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT M-ARA-90031313				