



- NOTES:**
- 1) ALL CURB RAMPS CONSTRUCTED SHALL HAVE DETECTABLE WARNINGS AND SHALL BE DYED FEDERAL STANDARD COLOR 30166 BRICK RED.
  - 2) ALL OFFSETS ARE TO THE BACK OF CURB ALONG THE EAST SIDE OF KEDZIE AVENUE.
  - 3) SIDEWALK ACROSS DRIVES SHALL BE 8" THICK.
  - 4) ALL PAVEMENT STRIPING SHALL BE THERMOPLASTIC PAVEMENT MARKINGS.
  - 5) ALL STEEL RAIL ELEMENTS SHALL BE GALVANIZED ACCORDING TO ARTICLE 509.05 OF THE STANDARD SPECIFICATIONS.

FILE NAME = H:\09\09-024\PLANS\PLAN.dwg	USER NAME =	DESIGNED - GGA/JDH	REVISED - 11-30-09
		DRAWN - GGA/BKL/BJS	REVISED -
		CHECKED - MAW	REVISED -
		DATE -	REVISED -
	PLOT SCALE =		
	PLOT DATE = 11/30/09 - 20:00 by Mark		

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**KEDZIE AVENUE FROM 153RD ST. TO 159TH ST.  
SIDEWALK CONSTRUCTION  
SIDEWALK PLAN**

SCALE: 1"=40'    SHEET NO. 5 OF 19 SHEETS    STA.    TO STA.

F.A.U. RTE. 2831	SECTION 09-00041-00-SW	COUNTY COOK	TOTAL SHEETS 19	SHEET NO. 5
CONTRACT NO. 63421				
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT ARA 9003(395)		