



LEGEND

- | | |
|--|---|
| | PROPOSED PCC SIDEWALK 5\"/> |
| | TOPSOIL, FURNISH AND PLACE, 4\"/> |
| | COMBINATION CURB AND GUTTER REMOVAL |
| | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 |
| | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18 |
| | TREE REMOVAL |
| | PERIMETER EROSION BARRIER |
| | DRIVEWAY PAVEMENT REMOVAL |
| | CLASS D PATCHES, TYPE 1, 9\"/> |
| | TREE REMOVAL |
| | DETECTABLE WARNING |
| | SIDEWALK REMOVAL |
| | BRICK PAVER REMOVAL |

NOTES

- SIDEWALK WIDTHS TO BE 5' UNLESS STATED OTHERWISE.
- OFFSETS ARE TAKEN FROM THE CENTERLINE OF SANGAMON STREET.
- PROPOSED SIDEWALK SHALL BE 5" DEPTH EXCEPT DRIVEWAY LOCATIONS SHALL BE 7" DEPTH AS INDICATED IN THE PLANS.

FILE NAME = 05612_01-PLAN-01 - SANGAMON	USER NAME =	DESIGNED -- JN/MN	REVISED --
		CHECKED -- JN/MN	REVISED --
PLOT SCALE =	DRAWN -- KWM	REVISED --	
PLOT DATE = 12-01-09	CHECKED -- KWM	REVISED --	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EXCHANGE ST. AND SANGAMON ST. SOUTHLAND SAFE ROUTE TO SCHOOL PROGRAM PLAN SHEET		F.A.U. RTE 1638	SECTION 06-00162-01-SW	COUNTY WILL	TOTAL SHEETS 17	SHEET NO. 3
SCALE: 1"=20'		SHEET NO. 3 OF 17 SHEETS		STA. TO STA.	CONTRACT NO. 63435	
		FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT CMM-9003 (077)	