

SUMMARY OF QUANTITIES			TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
CODE	ITEM	UNIT	80% FEDERAL 20% STATE 1000	80% FEDERAL 20% STATE X020-2A	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	179	179	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	55	55	
56109210	WATER VALVES TO BE ADJUSTED	EACH	2	2	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	81		81
60107600	PIPE UNDERDRAINS 4"	FOOT	60	60	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	150		150
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60242400	INLETS, SPECIAL	EACH	2	2	
60242801	INLETS, SPECIAL, NO. 5	EACH	4	4	
60255500	MANHOLES TO BE ADJUSTED	EACH	2	2	
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	5.0	5.0	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1,404	1,404	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
63200310	GUARDRAIL REMOVAL	FOOT	395	395	
63300705	RUB RAIL	FOOT	192	192	
63500105	DELINEATORS	EACH	8	8	
66411900	TEMPORARY FENCE	FOOT	597	597	
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8	8	
67100100	MOBILIZATION	L SUM	1	1	
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	

SUMMARY OF QUANTITIES			TOTAL QUANTITY	ROADWAY QUANTITY	BRIDGE QUANTITY
CODE	ITEM	UNIT	80% FEDERAL 20% STATE 1000	80% FEDERAL 20% STATE X020-2A	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	284	284	
70300625	TEMPORARY PAINT PAVEMENT MARKING LINE 4"	FOOT	4,745	4,745	
70300660	TEMPORARY PAINT PAVEMENT MARKING LINE 24"	FOOT	63	63	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,133	1,133	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1,088	1,088	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1,063	1,063	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	11,592	11,592	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	74	74	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	11	11	
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	4	4	
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	4	4	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	198	198	
* A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	3	3	
X0712400	TEMPORARY PAVEMENT	SQ YD	404	404	
X0919000	TEMPORARY PAVEMENT REMOVAL	SQ YD	404	404	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1		1
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	

△ NON-PARTICIPATING
* SPECIALTY ITEMS

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL. ROUTE 70 OVER OTTER CREEK
SUMMARY OF QUANTITIES

HOH		HARRY O. KEFFER-ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS		55 East Jackson Blvd. Suite 500 Chicago, IL 60604 312-367-8100	PROJECT NUMBER 2944
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
55	(W-1-15d)BR-1	WINNEBAGO	59	5	
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 64D22		

FILE NAME =	USER NAME = conderman	DESIGNED - AAF	REVISED -
C:\Documents and Settings\conderman\Local Settings\Temporary Internet Files\Content.IE5\...CRAWN\VPURB\H00A\6207soq (2).dgn	CHECKED - BAP	DATE - Wed Dec 02 14:27:59 2009	REVISED -
PLOT SCALE = 20.0000' / IN.	DATE - Wed Dec 02 14:27:59 2009		

SCALE: NONE SHEET NO. 2 OF 2 SHEETS STA. N/A TO STA. N/A