

20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)			REMARKS
	UNITS	LOCATION	OFFSET	
	12	64+92	36' LT	
	12	64+93	43' LT	
	24	TOTAL		

20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)			REMARKS
	UNITS	LOCATION	OFFSET	
	18	65+71	34' LT	
	18	TOTAL		

28000305	TEMPORARY DITCH CHECKS			REMARKS
	FOOT	LOCATION	OFFSET	
	17.5	58+28	RT	
	17.5	60+28	RT	
	17.5	62+28	RT	
	17.5	62+97	LT	
	17.5	62+98	RT	
	17.5	64+97	LT	
	105	TOTAL		

28000400	PERIMETER EROSION BARRIER			REMARKS
	FOOT	LOCATION	OFFSET	
	27	57+66 TO 57+79	LT	
	425	57+98 TO 62+50	LT	
	166	62+82 TO 64+48	RT	
	30	64+72 TO 65+02	RT	
	34	65+24 TO 65+58	RT	
	36	65+64 TO 66+00	RT	
	718	TOTAL		

28000500	INLET AND PIPE PROTECTION			REMARKS
	EACH	LOCATION	OFFSET	
	1	64+82	26' LT	
	1	64+75	23' RT	
	1	65+28	24' RT	
	3	TOTAL		

40201000	AGGREGATE FOR TEMPORARY ACCESS			REMARKS
	TONS	LOCATION	OFFSET	
	106	64+50 TO 66+00	RT	STAGE 1
	84	57+65 TO 58+50	LT	STAGE 2
	83	64+60 TO 66+00	LT	STAGE 2
	273	TOTAL		

40600990	TEMPORARY RAMP			REMARKS
	SQ YD	LOCATION	OFFSET	
	497	57+65 TO 61+91	RT	STAGE 2 ALONG GUTTER
	329	63+18 TO 66+00	RT	STAGE 2 ALONG GUTTER
	12	57+65	LT	STAGE 3 PRIOR TO SURFACE COURSE
	12	61+91	LT	STAGE 3 PRIOR TO SURFACE COURSE
	12	63+18	LT	STAGE 3 PRIOR TO SURFACE COURSE
	12	66+00	LT	STAGE 3 PRIOR TO SURFACE COURSE
	874	TOTAL		

44000100	PAVEMENT REMOVAL			REMARKS
	SQ YD	LOCATION	OFFSET	
	660	57+65 TO 62+25	LT	
	660	57+65 TO 62+25	RT	
	428	63+06 TO 66+00	LT	
	428	63+06 TO 66+00	RT	
	2,176	TOTAL		

44000600	SIDEWALK REMOVAL			REMARKS
	SQ FT	LOCATION	OFFSET	
	45	57+94 TO 58+08	LT	
	17	65+61 TO 65+63	RT	
	62	TOTAL		

48100100	AGGREGATE SHOULDERS, TYPE A			REMARKS
	TON	LOCATION	OFFSET	
	8.8	56+65 TO 57+58	LT	PLACE WHERE TEMP PAVEMENT WAS REMOVED
	9.5	56+65 TO 57+65	RT	PLACE WHERE TEMP PAVEMENT WAS REMOVED
	7.7	66+29 TO 67+10	LT	PLACE WHERE TEMP PAVEMENT WAS REMOVED
	9.5	66+00 TO 67+00	RT	PLACE WHERE TEMP PAVEMENT WAS REMOVED
	36	TOTAL		

50105200	REMOVE EXISTING CULVERTS			REMARKS
	EACH	LOCATION	OFFSET	
	1	65+13	RT	INCLUDES HEADWALL REMOVAL (2 EACH)
	1	TOTAL		

56109210	WATER VALVES TO BE ADJUSTED			REMARKS
	EACH	LOCATION	OFFSET	
	1	60+88	47' LT	
	1	65+12	28' LT	
	2	TOTAL		

60107600	PIPE UNDERDRAINS 4"			REMARKS
	FOOT	LOCATION	OFFSET	
	16	59+80	LT	
	16	59+80	RT	
	14	63+30	LT	
	14	63+30	RT	
	60	TOTAL		

60255500	MANHOLES TO BE ADJUSTED			REMARKS
	EACH	LOCATION	OFFSET	
	1	58+61	28' LT	
	1	60+17	28' LT	
	2	TOTAL		

63100085	TRAFFIC BARRIER TERMINAL, TYPE 6			REMARKS
	EACH	LOCATION	OFFSET	
	1	61+45 TO 61+90	LT	
	1	61+59 TO 62+05	RT	
	1	63+18 TO 63+64	LT	
	1	63+03 TO 63+49	RT	
	4	TOTAL		

63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT			REMARKS
	EACH	LOCATION	OFFSET	
	1	60+95 TO 61+45	LT	
	1	61+09 TO 61+59	RT	
	1	63+64 TO 64+14	LT	
	1	63+49 TO 63+99	RT	
	4	TOTAL		

63200310	GUARDRAIL REMOVAL			REMARKS
	FOOT	LOCATION	OFFSET	
	98	61+27 TO 62+25	LT	
	99	61+26 TO 62+25	RT	
	99	63+06 TO 64+05	LT	
	99	63+06 TO 64+05	RT	
	395	TOTAL		

63300705	RUB RAIL			REMARKS
	FOOT	LOCATION	OFFSET	
	96	60+95 TO 61+90	LT	
	96	63+18 TO 64+14	LT	
	192	TOTAL		

63500105	DELINEATORS			REMARKS
	EACH	LOCATION	OFFSET	
	1	57+55	LT	C&G INLET
	1	57+65	RT	C&G INLET
	1	60+94	LT	GUARDRAIL TERMINAL
	1	61+08	RT	GUARDRAIL TERMINAL
	1	64+00	RT	GUARDRAIL TERMINAL
	1	64+13	LT	GUARDRAIL TERMINAL
	1	66+01	LT	C&G INLET
	1	66+02	RT	C&G INLET
	8	TOTAL		

FILE NAME = H:\Pro\jects\2944\DNIS\206287SCH1.dgn	USER NAME = #USER#	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE = 12/16/2009	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**IL ROUTE 70 OVER OTTER CREEK
SCHEDULE OF QUANTITIES**

HOH		HARRY G. NEFFER-ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS		38 East Jackson Blvd. Suite 600 Chicago, IL 60604 312-344-9131		PROJECT NUMBER 2944
F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
55	(W-1-15d)BR-1	WINNEBAGO	59	8		
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT			
CONTRACT NO. 64022						