

66411900	TEMPORARY FENCE				OFFSET	REMARKS
FOOT	LOCATION					
479	57+66	TO	62+45	RT	PLACE ALONG TEMP. ESMT WITHIN SCHOOL PROPERTY	
118	62+82	TO	64+00	RT	PLACE ALONG TEMP. ESMT WITHIN SCHOOL PROPERTY	
<b>597</b>	<b>TOTAL</b>					

66700305	PERMANENT SURVEY MARKERS, TYPE II				OFFSET	REMARKS
EACH	LOCATION					
1	57+60				EXACT LOCATION TBD BY RESIDENT ENGINEER	
1	BRIDGE				EXACT LOCATION TBD BY RESIDENT ENGINEER	
1	66+00				EXACT LOCATION TBD BY RESIDENT ENGINEER	
<b>3</b>	<b>TOTAL</b>					

70300100	SHORT-TERM PAVEMENT MARKING				OFFSET	REMARKS
FOOT	LOCATION					
284	54+74	TO	68+91		2 APPLICATIONS	
<b>284</b>	<b>TOTAL</b>					

70300625	TEMPORARY PAINT PAVEMENT MARKING - LINE 4"				OFFSET	REMARKS
FOOT	LOCATION					
1364	54+69	TO	68+33	LT	STAGE 1, WHITE LEFT EDGE	
1040	56+61	TO	67+01	RT/LT	STAGE 1, WHITE RIGHT EDGE	
1329	55+45	TO	68+74	RT/LT	STAGE 2, WHITE LEFT EDGE	
1012	56+75	TO	66+87	LT	STAGE 2, WHITE RIGHT EDGE	
<b>4,745</b>	<b>TOTAL</b>					

70300660	TEMPORARY PAINT PAVEMENT MARKING - LINE 24"				OFFSET	REMARKS
FOOT	LOCATION					
13	53+73			RT	USE FOR STAGES 1&2	
17	53+92	TO	54+09	LT	USE FOR STAGES 1&2 @ SOUTH ST.	
20	54+09	TO	55+29	RT	USE FOR STAGES 1&2 @ SOUTH ST.	
13	68+97			LT	USE FOR STAGES 1&2	
<b>63</b>	<b>TOTAL</b>					

70301000	WORK ZONE PAVEMENT MARKING REMOVAL				OFFSET	REMARKS
SQ.FT	LOCATION					
35	56+61	TO	57+65	LT LINE	STAGE 1, LEFT EDGE LINE	
99	54+69	TO	57+65	RT LINE	STAGE 1, RIGHT EDGE LINE	
34	66+00	TO	67+01	LT LINE	STAGE 1, LEFT EDGE LINE	
78	66+00	TO	68+33	RT LINE	STAGE 1, RIGHT EDGE LINE	
443	55+45	TO	68+74	LT LINE	STAGE 2, LEFT EDGE LINE	
333	56+75	TO	66+75	RT LINE	STAGE 2, RIGHT EDGE LINE	
48	54+69	TO	68+75	CENTER	STOP BAR	
13	53+74			LT	STOP BAR	
17	53+92	TO	54+09	LT	SOUTH ST. STOP BAR	
20	54+09	TO	55+29	RT	SOUTH ST. STOP BAR	
13	68+97			RT LINE	SHORT TERM PAVEMENT MARKINGS ON TOP LIFT	
<b>1,133</b>	<b>TOTAL</b>					

70400100	TEMPORARY CONCRETE BARRIER				OFFSET	REMARKS
FOOT	LOCATION					
1087.5	56+37.5	TO	67+25.0		STAGE 1 MOT	
<b>1,087.5</b>	<b>TOTAL</b>					

70400200	RELOCATE TEMPORARY CONCRETE BARRIER				OFFSET	REMARKS
FOOT	LOCATION					
1062.5	56+50.0	TO	67+12.5		STAGE 2 MOT	
<b>1,062.5</b>	<b>TOTAL</b>					

78001110	PAINT PAVEMENT MARKING - LINE 4"				OFFSET	REMARKS
FOOT	LOCATION					
2728	54+69	TO	68+33	LT	WHITE EDGE LINE-2 APPLICATIONS	
2728	54+69	TO	68+33	RT	WHITE EDGE LINE-2 APPLICATIONS	
5456	54+69	TO	68+33	CENTER	DOUBLE YELLOW-2 APPLICATIONS	
680	54+69	TO	68+33	CENTER	SKIP DASH-YELLOW-2 APPLICATIONS	
<b>11,592</b>	<b>TOTAL</b>					

78001180	PAINT PAVEMENT MARKING - LINE 24"				OFFSET	REMARKS
FOOT	LOCATION					
34	53+92	TO	54+09	LT	WHITE STOP BAR @ SOUTH ST.-2 APPLICATIONS	
40	54+09	TO	54+29	RT	WHITE STOP BAR @ SOUTH ST.-2 APPLICATIONS	
<b>74</b>	<b>TOTAL</b>					

78100100	RAISED REFLECTIVE PAVEMENT MARKER				OFFSET	REMARKS
EACH	LOCATION					
11	57+65	TO	66+00		2 WAY AMBER 80' C-C	
<b>11</b>	<b>TOTAL</b>					

78200410	GUARDRAIL MARKERS, TYPE A				OFFSET	REMARKS
EACH	LOCATION					
1	61+60			RT		
1	61+70			LT		
1	63+40			RT		
1	62+50			LT		
<b>4</b>	<b>TOTAL</b>					

78200520	BARRIER WALL MARKERS, TYPE B				OFFSET	REMARKS
EACH	LOCATION					
1	62+20			RT		
1	62+30			LT		
1	62+80			RT		
1	62+90			LT		
<b>4</b>	<b>TOTAL</b>					

78201000	TERMINAL MARKER - DIRECT APPLIED				OFFSET	REMARKS
EACH	LOCATION					
1	60+95			LT		
1	61+09			RT		
1	64+14			LT		
1	63+99			RT		
<b>4</b>	<b>TOTAL</b>					

78300100	PAVEMENT MARKING REMOVAL				OFFSET	REMARKS
SQ.FT	LOCATION					
181	54+69	TO	57+40	CENTER	DOUBLE YELLOW CENTER LINE	
17	66+25	TO	68+33	CENTER	SKIP-DASH YELLOW CENTER LINE	
<b>198</b>	<b>TOTAL</b>					

X0712400	TEMPORARY PAVEMENT				OFFSET	REMARKS
SQ.YD	LOCATION					
192	56+50	TO	62+25	LT	STAGE 1	
136	63+06	TO	67+10	LT	STAGE 1	
38	56+65	TO	57+77	RT	STAGE 2	
38	65+88	TO	67+00	RT	STAGE 2	
<b>404</b>	<b>TOTAL</b>					

X0919000	TEMPORARY PAVEMENT REMOVAL				OFFSET	REMARKS
SQ.YD	LOCATION					
192	56+50	TO	62+25	LT	STAGE 1	
136	63+06	TO	67+10	LT	STAGE 1	
38	56+65	TO	57+77	RT	STAGE 2	
38	65+88	TO	67+00	RT	STAGE 2	
<b>404</b>	<b>TOTAL</b>					

Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3				OFFSET	REMARKS
EACH	LOCATION					
1	56+37.5			RT	STAGE 1 MOT (USE NARROW DEVICE)	
1	67+25			RT	STAGE 1 MOT (USE NARROW DEVICE)	
<b>2</b>	<b>TOTAL</b>					

Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3				OFFSET	REMARKS
EACH	LOCATION					
1	56+50			LT	STAGE 2 MOT	
1	67+12.5			LT	STAGE 2 MOT	
<b>2</b>	<b>TOTAL</b>					

FILE NAME = H:\Projects\2944\DDNS\Z06207SCH1.dgn	USER NAME = #USER#	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE - 11/30/2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

IL ROUTE 70 OVER OTTER CREEK  
SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

<b>HOH</b>		HARRY O. HESTER ASSOCIATES, INC. DESIGN AND CONSULTING ENGINEERS 35 East Jackson Blvd. Suite 600 Chicago, IL 60604 312-516-8121		PROJECT NUMBER <b>2944</b>
F.A.P. RTE. 55	SECTION (W-1-15)BR-1	COUNTY WINNEBAGO	TOTAL SHEETS 59	SHEET NO. 9
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 64D22		