

SUMMARY OF QUANTITIES

ROADWAY
J000-2A
80% FED 20%
STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY
20100500	TREE REMOVAL, ACRES	ACRE	6
20200100	EARTH EXCAVATION	CU YD	25568
20200200	ROCK EXCAVATION	CU YD	14586
20400800	FURNISHED EXCAVATION	CU YD	38863
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	47940
25000210	SEEDING, CLASS 2A	ACRE	7.25
25000310	SEEDING, CLASS 4	ACRE	3
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	900
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	900
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	900
25000750	MOWING	ACRE	7.25
25100115	MULCH, METHOD 2	ACRE	10.25
25100630	EROSION CONTROL BLANKET	SQ YD	14638
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	15000
28000305	TEMPORARY DITCH CHECKS	FOOT	3848
28000400	PERIMETER EROSION BARRIER	FOOT	374
28000500	INLET AND PIPE PROTECTION	EACH	4
28100105	STONE RIPRAP, CLASS A3	SQ YD	6765
28100107	STONE RIPRAP, CLASS A4	SQ YD	9435
28200200	FILTER FABRIC	SQ YD	16200
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	19637
31100935	SUB-BASE GRANULAR MATERIAL, TYPE A 18"	SQ YD	969
31100975	SUB-BASE GRANULAR MATERIAL, TYPE A 30"	SQ YD	1822
35101400	AGGREGATE BASE COURSE, TYPE B	TON	822
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	121
42000416	PORTLAND CEMENT CONCRETE PAVEMENT 9 3/4" (JOINTED)	SQ YD	13292
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	16
44000100	PAVEMENT REMOVAL	SQ YD	3093
44000400	GUTTER REMOVAL	FOOT	144
44004000	PAVED DITCH REMOVAL	FOOT	210
44004300	PAVEMENT BREAKING	SQ YD	10711

+

* SPECIALTY ITEMS
† NON PARTICIPATING 100% STATE

FILE NAME =	USER NAME = cushmanbw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pw_work\pwsdot\cushmanbw\d2117386\022808-shc-schedule.dgn		DRAWN -	REVISED -			301	31T	JO DAVIESS	160	3	
PLOT SCALE = 50.0000 ' / IN.		CHECKED -	REVISED -			CONTRACT NO. 64D92					
PLOT DATE = Wed Dec 09 13:58:37 2009		DATE -	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO

ILLINOIS FED. AID PROJECT