

EARTHWORK /SEEDING SCHEDULE

LOCATION	20200100	20200200	20400800				25000210	25000310	25000400	25000500	25000600	25000750	25100115	28000250	21101615
	EARTH EXCAVATION	ROCK EXCAVATION	FURNISHED EXC	EARTH EXC ADJ SHRINK 25% EARTH	EMBANK (FILL)	EARTH WORK BALANCE WASTE (+) SHORTAGE (-)	SEEDING CLASS 2A	SEEDING CLASS 4	NITROGEN FERTILIZER NUTRIENTS	PHOSPHOROUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS		MULCH METHOD 2	TEMPORARY EROSION CONTROL SEEDING	TOPSOIL FURNISH & PLACE 4"
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	ACRE	ACRE	POUND	POUND	POUND	ACRE	ACRE	POUNDS	SQ YD
232 +00 - 245 +00	955		10776	716	11492	-10775	1.25	0.25	135.00	135.00	135.00	1.25	1.50	2250.00	7245
245 +00 - 259 +00	2576	6631	29516	1932	38079	-36148	4.01	0.98	449.10	449.10	449.10	4.01	4.99	7485.00	24152
259 +00 - 273 +00	3112	7955	11922	2334	22211	-19877	0.70	0.44	102.60	102.60	102.60	0.70	1.14	1710.00	5516
273 +00 - 279 +78.45	18759			14069	719	13351	0.54	1.08	145.80	145.80	145.80	0.54	1.62	2430.00	7108
Temporary West Crossover	157			117	74	43	0.50		45.00	45.00	45.00	0.50	0.50	750.00	2420
Temp. Pvt. & Ditch Grading near Main St.(Estimated)	10		43	8	50	-43	0.25	0.25	22.50	22.50	22.50	0.25	0.50	375.00	1500
TOTAL	25568	14586	38863	19176	72625	-53449	7.25	3.00	900	900	900	7.25	10.25	15000	47940

PAVING SCHEDULE

Location	Remarks	Length	Proposed Surface		X0712400	X0919000	42000416	48300415
			Width	Sq Yd	Temporary Pavement	Temporary Pavement Removal	Portland Cement Conc. Pavement 9 3/4" (Jointed)	Portland Cement Conc. Shoulders, 9 3/4"
					SY YD	SY YD	Sq Yd	Sq Yd
US 20								
Lt & Rt Sta	232+ 00 - 278+ 75	4675	24	12467			12466.67	
CROSSOVER								
Lt & Rt Sta	0+ 00 - 1+ 38	138	VAR	400			400.00	
ACCESS RD A								
Lt & Rt Sta	0+ 12 - 0+ 96	84	VAR	425			425.00	70
Shoulders								
Lt. Sta	232+ 00 - 245+ 78	1378	6	919				918.7
Lt. Sta	246+ 56 - 275+ 11	2855	6	1903				1903.3
Lt. Sta	276+ 50 - 278+ 75	225	6	150				150.0
Rt. Sta	232+ 00 - 278+ 75	4675	10	5194				5194.4
Crossover								
West Crossover	0+ 73 - 7+ 03	0	VAR	586	586	586		
East Crossover			VAR	171	171			
SW Quadrant of Main St.	Widening Radius Return			141	159			
TOTALS					916	586	13,292	8,236