SCHEDULE OF QUANTITIES

44000100 PAVEMENT REMOVAL

SQ YD	LOCATION	
	NW Return	
8.32	LT	625+92.67
666.92	NE Return	168+41.88 – 627+56.25
	US Rte 30	
351.92	LT	627+56.25 – 631+00.01
1,027		

44000500 COMBINATION CURB AND GUTTER REMOVAL

FOOT	LOCATION	
	NW Return	
37.50	LT	625+92.71 – 626+03.82
	NE Return	
110.00	LT	626+37.22 – 626+75.1
147.50		

44004250 PAVED SHOULDER REMOVAL

SQ YD	LOCATION	
50.00	SW Return	625+47.55 – 301+45.49
60.92	NW Return	624+51.96 – 168+41.38
67.72	NE Return	168+41.88 – 627+56.25
	IL Rte 136	
39.19	LT & RT	166+65.01 – 168+41.38
	US Rte 30	
262.92	LT	627+56.25 – 635+45.01
481		

50104400 CONCRETE HEADWALL REMOVAL

EACH	LOCATION	
	NW Return	
1	RT	168+56.42
	NE Return	
1	LT	168+56.42
	US Rte 30	
1	LT	634+86.54
3		

54213453 END SECTIONS 18"

EACH	LOCATION	
	SW Return	
1.00	LT	300+71.3
1		

54213669 PRECAST REINFORCED CONCRETE FLARED END SECTION 24"

EACH	LOCATION		OFFSET
	NW Return		
1.00	RT	168+56.42	27'
	NE Return		
1.00	LT	168+56.42	27'
2			

54213681 PREACST REINFORCED CONCRETE FLARED END SECTION 36"

EACH	LOCATION		OFFSET
	US Rte 30		
1.00	LT	634+86.54	30'
1			

542A0229 PIPE CULVERTS, CLASS A, TYPE 1 24"

FOOT	LOCATION		OFFSET
	NW Return		
2.00	RT	168+56.42	25' – 27'
	NE Return		
2.00	LT	168+56.42	25' – 27'
4			

542D0223 PIPE CULVERTS, CLASS D, TYPE 1 18"

FOOT	LOCATION		OFFSET
	SW Return		
8.00	RT	300+71.3	28' – 36'
8.00			

60618300 CONCRETE MEDIAN SURFACE, 4 INCH

SQ FT	LOCATION		OFFSET
	NW Return		
68.51	LT	625+87.27 – 625+98.18	27'
	NE Return		
687.89	LT	626+56.7 – 627+09.25	32'
756.40			

63500310 REMOVE AND REINSTALL DELINEATORS

EACH	LOCATION	
	US Rte 30	
1	LT	634+86.54
	NW Return	
1	RT	168+56.42
	NE Return	
1	LT	168+56.42
	SW Return	
1	LT	300+71.3
4		

FILE NAME = c:\pw_work\PWIDOT\HENSONKE\d0128026\p01708cvr.dgn	USER NAME = hensonke	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Wed Dec 02 10:12:31 2009	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

US RTE 30
SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
309	(20-1)M	WHITESIDE	53	10
		CONTRACT NO. 64F37		
	ILLINOIS	FED. AID PROJECT		