

SCHEDULE OF QUANTITIES

78000100 THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS

SQ. FT	LOCATION		OFFSET
	US Rte 30		
15.60	LT	627 + 75.34	42.90'
15.60	LT	628 + 75.15	39.40'
15.60	LT	629 + 74.48	32.48'
15.60	LT	630 + 73.81	26.96'
15.60	LT	631 + 73.31	23.18'
15.60	LT	632 + 72.89	21.14'
<u>93.60</u>			

78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4"

FOOT	LOCATION	
150.81	SW Return	625 + 47.55 - 301 + 45.49
213.74	NW Return	624 + 51.96 - 168 + 41.38
203.15	NE Return	168 + 41.88 - 627 + 56.25
	IL Rte 136	
450.83	RT & LT	166 + 65.01 - 168 + 41.38
195.74	CL	168 + 34.35 - 169 + 32.22
	US Rte 30	
788.75	LT	627 + 56.25 - 635 + 45.01
	Frog Pond Road	
206.96	CL	300 + 35.87 - 301 + 39.35
<u>2,209.98</u>		

78000500 THERMOPLASTIC PAVEMENT MARKING - LINE 8"

FOOT	LOCATION		OFFSET
	US Rte 30		
188.20	LT	625 + 42.26 - 626 + 01.03	12' - 16'
1,319.64	LT	626 + 42.73 - 632 + 80.01	12' - 18'
88.33	LT	632 + 80.01 - 635 + 45.01	12' - 11.62'
<u>1,596.17</u>			

78000600 THERMOPLASTIC PAVEMENT MARKING - LINE 12"

FOOT	LOCATION		OFFSET
	US Rte 30		
76.40	LT	625 + 42.26 - 626 + 01.03	12' - 16'
403.65	LT	626 + 42.73 - 632 + 80.01	12' - 18'
	IL Rte 136		
16.60	CL	168 + 34.35 - 169 + 32.22	0' - 4'
	Frog Pond Road		
18.70	CL	300 + 35.87 - 301 + 39.35	0' - 4'
<u>515.35</u>			

78000650 THERMOPLASTIC PAVEMENT MARKING - LINE 24"

FOOT	LOCATION		OFFSET
	IL Rte 136		
18.00	RT	169 + 02.05	45'
12.00	RT	169 + 32.22	4'
	Frog Pond Road		
12.00	RT	300 + 26.05	0'
21.00	RT	300 + 31.9	29'
<u>63.00</u>			

78100100 RAISED REFLECTIVE PAVEMENT MARKER

EACH	LOCATION		OFFSET
	IL Rte 136		
7.00	CL	166 + 65.01 - 169 + 36.94	
	Frog Pond Road		
7.00	CL	300 + 35.87 - 301 + 39.35	
	US Rte 30		
30.00	LT	626 + 42.73 - 632 + 05.42	11.5'
27.00	LT	627 + 00.01 - 632 + 05.42	34'-14'
<u>71.00</u>			

78300200 RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

EACH	LOCATION		OFFSET
	IL Rte 136		
5.00	CL	166 + 65.01 - 169 + 36.94	
<u>5.00</u>			

78300100 PAVEMENT MARKING REMOVAL

SQ. FT	LOCATION	
	US Rte 30	
163.19	LT	626 + 39.28 - 628 + 84.06
148.62	LT	630 + 99.15 - 635 + 45.01
50.00	SW Return	625 + 47.35 - 301 + 45.49
75.60	NW Return	624 + 51.96 - 168 + 41.38
	Frog Pond Road	
68.99	CL	300 + 35.87 - 301 + 39.35
<u>506.40</u>		

X0323221 PLUG & ABANDON EXISTING PIPE

CJ. YD	LOCATION		OFFSET
	NW Return		
0.75	LT	625 + 75.01 - 625 + 90.67	39.7' - 31.09'
<u>0.75</u>			

X0325519 DRAIN FOR AGGREGATE BASE COURSE

SQ. YD	LOCATION	
	US Rte 30	
2.67	LT	633 + 00.
2.33	LT	628 + 00.
2.00	NE Return	626 + 45.74
	NW Return	
3.67	RT	168 + 83.05
3.33	LT	626 + 10.
0.75	LT	625 + 75.01 - 625 + 90.67
2.00	SW Return	301 + 24.53
2.00	IL Rte 136	167 + 50.
<u>18.75</u>		