

SCHEDULE OF QUANTITIES

X0349800 CONCRETE HEADWALL FOR PIPE UNDERDRAIN REMOVAL

EACH	LOCATION		OFFSET
1	NW Return		
	LT	625 + 61.52	50'
1	NE Return		
	LT	626 + 72.33	75'
<u>2</u>			

X6064201 COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.06

FOOT	LOCATION		OFFSET
38.00	NW Return		
	LT	625 + 85.13 - 626 + 00.21	27'
147.00	NE Return		
	LT	626 + 57.89 - 627 + 20.34	33'
<u>185</u>			

XX003964 REMOVAL OF EXISTING METAL END SECTIONS

EACH	LOCATION		OFFSET
1	SW Return		
1	RT	300 + 71.30	34'

Z0014800 CULVERT TO BE CLEANED

FOOT	LOCATION		OFFSET
60	SW Return		
	LT & RT	300 + 71.3	
50	NW Return		
	LT & RT	168 + 56.42	
66	US Rte 30		
	LT & RT	634 + 86.54	
<u>176</u>			

Z0028415 GEOTECHNICAL REINFORCEMENT

SQ YD	LOCATION		OFFSET
153.65	SW Return	625 + 47.55 - 301 + 45.49	
548.31	NW Return	624 + 51.96 - 168 + 41.38	
1004.03	NE Return	168 + 41.88 - 627 + 56.25	
109.72	IL Rte 136		
	RT	166 + 06.02 - 168 + 41.38	
146.45	LT	166 + 06.03 - 168 + 41.88	
	US Rte 30		
1,948.02	LT	627 + 56.25 - 635 + 45.01	
<u>3,910</u>			

Z0040530 PIPE UNDERDRAIN REMOVAL

FOOT	LOCATION		OFFSET
16.00	NW Return		
	LT	625 + 61.29 - 625 + 75.01	47.22' - 39.73'
7.00	LT	625 + 90.67 - 625 + 96.71	31.09' - 27.91'
	NE Return		
41.00	LT	626 + 52.84 - 626 + 72.49	35.00' - 74.5'
	<u>64</u>		

Z0055100 RUMBLE RESURFACING

SQ YD	LOCATION		OFFSET
32.26	IL Rte 136		
	LT	163 + 06.41 - 163 + 31.41	
32.26	LT	164 + 32.22 - 164 + 57.22	
	LT	166 + 32.22 - 166 + 57.22	
<u>97</u>			