

PATCHING SCHEDULE

LOCATION	REMARKS				44200553		44200557		44200559		44213000		44213200		Z0075300		Z0005400		31100300		X0325519		
		STA TO STA	LENGTH FT	WIDTH FT		CLASS A PATCHES TYPE II, 10 INCH SQ YD		CLASS A PATCHES TYPE III, 10 INCH SQ YD		CLASS A PATCHES TYPE IV, 10 INCH SQ YD		PATCHING REINFORCEMENT SQ YD		SAW CUTS FOOT		TIE BARS EACH		12" BREAKER-RUN CRUSHED STONE TON		SUB-BASE GRAN MATERIAL TY A 4" SQ YD		DRAIN FOR AGG BSE COURSE SQ YD	
				INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE
North Bound																							
665 + 50 - 665 + 56		6	12	12		8					8		60										
691 + 50 - 691 + 58	Patch 1/2 Lane Long. Crack	8	6	6		5					5		40										
693 + 0 - 694 + 0	Patch 1/2 Lane Long. Crack	100	6	6						67	67		224		51		28.2		21.3		7.0		
700 + 50 - 703 + 30	Patch 1/2 Lane Long. Crack	280	6	6						187	187		584		141		77.3		61.3		16.3		
705 + 50 - 706 + 50	Patch 1/2 Lane Long. Crack	100	6	6						67	67		224		51		28.2		21.3		7.0		
707 + 50 - 709 + 50	Patch 1/2 Lane Long. Crack	200	6	6						133	133		424		101		54.9		43.6		11.7		
710 + 0 - 713 + 0	Patch 1/2 Lane Long. Crack	300	6	6						200	200		624		151		81.7		65.8		16.3		
723 + 50 - 727 + 50	Patch 1/2 Lane Long. Crack	400	6	6						267	267		824		201								
727 + 80 - 728 + 80	Patch 1/2 Lane Long. Crack	100	6	6						67	67		224		51								
729 + 0 - 733 + 0	Patch 1/2 Lane Long. Crack	400	6	6						267	267		824		201								
751 + 75 - 757 + 0	Patch 1/2 Lane Long. Crack	525	6	6						350	350		1074		264								
751 + 75 - 757 + 0	REST AREA - RAMP	525	6	6						350	350		1074		264								
757 + 60 - 758 + 0		40	12	12						53	53		128		21								
759 + 0 - 759 + 80		80	12	12						107	107		208		41								
762 + 0 - 762 + 80		80	12	12						107	107		208		41								
774 + 60 - 775 + 0		40	12	12						53	53		128		21								
777 + 90 - 778 + 0		10	12	12		13					13		68										
788 + 50 - 788 + 56		6	12	12		8					8		60										
788 + 75 - 789 + 15		40	12	12						53	53		128		21								
800 + 20 - 800 + 26		6	12	12		8					8		60										
839 + 20 - 839 + 26		6	12	12		8					8		60										
845 + 80 - 846 + 20		40	12	12						53	53		128		21								
846 + 80 - 847 + 20		40	12	12						53	53		128		21								
848 + 0 - 848 + 50		50	12	12						67	67		148		26								

NOTE: STATIONS ARE APPROXIMATE AND ARE SUBJECT TO CHANGE BY THE RE/TE

FILE NAME =	USER NAME = stringerjm	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-39 PATCHING SCHEDULE	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci\pw_work\PWIDOT\STRINGERJM\d0162099\	202110-ah-t-schedule.dgn	DRAWN -	REVISED -		39	*	LEE	60	12	
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 64F82					
PLOT DATE = Tue Feb 16 11:21:48 2010	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					

Rev. Sheet 2-16-10