

# SHOULDER SCHEDULE

LOCATION	REMARKS	SHOULDERS			Z0010800		20200600		48100100		48300300		63500205
		STA TO STA	LENGTH	WIDTH		COLD MILLING (SPECIAL)	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE A		PCC SHOULDERS 8"		REM AND REPLACING DELINEATORS	
				FT	FT			FT	TON		SQ YD		
		FT	FT	FT	SQ YD	UNIT	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	EACH
North Bound			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	OUTSIDE
877 + 96 - 878 + 8	Approach Shldr Omission	12	6	10									
878 + 8 - 889 + 38		1130.7	6	10	754	1256	11	11	201	144	754	1256	4
889 + 38 - 891 + 73	US 30 - Ramp & Gore	234.6	6	6	156	366	2	2	42	30	156	366	3
891 + 73 - 901 + 33	US 30 - Ramp	959.8	6	6 & Var.	640	703	10	10	171	122	640	703	11
901 + 33 - 1178 + 90		27757.4	6	10	18505	30842	278	278	4932	3541	18505	30842	70
1178 + 90 - 1179 + 24	Approach Shldr Omission	34.2	6	10									
1179 + 24 - 1180 + 87	Steward Cr. Br. Omission	162.6	6	10									
1180 + 87 - 1181 + 19	Approach Shldr Omission	31.5	6	10									
1181 + 19 - 1187 + 15		596.3	6	10	398	707	6	6	106	76	398	707	2
1187 + 15 - 1187 + 32	Approach Shldr Omission	16.8	6	10									
1187 + 32 - 1189 + 1	BN & SF RR Br. Omission	169.4	6	10									
1189 + 1 - 1189 + 7	Approach Shldr Omission	6	6	10									
1189 + 7 - 1193 + 9		401.6	6	10	268	446	4	4	71	51	268	446	2
1193 + 9 - 1193 + 21	Approach Shldr Omission	12.7	6	10									
1193 + 21 - 1194 + 84	Perry Rd Bridge Omission	162.3	6	10									
1194 + 84 - 1194 + 96	Approach Shldr Omission	11.9	6	10									
1194 + 96 - 1198 + 32	Perry Rd - Ramp	336.3	6	6 & Var	224	245	3	3	60	43	224	245	4
1198 + 32 - 1201 + 95	Perry Rd - Ramp	363.3	6	6	242	239	4	4	65	46	242	239	5
1201 + 95 - 1214 + 17	Perry Rd Between Ramps	1221.4	6	8	814	1086	12	12	217	156	814	1086	4
1214 + 17 - 1216 + 18	Perry Rd - Ramp & Gore	201.8	6	6	135	242	2	2	36	26	135	242	3

FILE NAME =	USER NAME = dossed	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>I-39</b> <b>SHOULDER SCHEDULE</b>	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ca\pwwork\PWIDOT\DOSSDD\10162099\020210-shd-schedule.dgn		DRAWN -	REVISED -			39	*	LEE	60	7	
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AID PROJECT			
PLOT DATE = Wed Dec 30 15:20:43 2009		DATE -	REVISED -					CONTRACT NO. 64F82			