

SHOULDER SCHEDULE

LOCATION	REMARKS	SHOULDERS			Z0010800		20200600		48100100		48300300		63500205
		LENGTH	WIDTH		COLD MILLING (SPECIAL)	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE A	PCC SHOULDERS 8"	REM AND REPLACING DELINEATORS				
			FT	FT						FT	SQ YD	UNIT	TON
STA TO STA			INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	INSIDE	OUTSIDE	OUTSIDE
South Bound													
865 + 4 - 876 + 5		1100.9	6	10	734	1223	11	11	196	140	734	1223	4
876 + 5 - 876 + 17	Approach Shldr Omission	12	6	10									
876 + 17 - 877 + 99	US 30 Bridge Omission	181.9	6	10									
877 + 99 - 878 + 11	Approach Shldr Omission	12	6	10									
878 + 11 - 891 + 24		1313.1	6	10	875	1459	13	13	233	167	875	1459	4
891 + 24 - 895 + 20	US 30 - Ramp	396.3	6	6	264	290	4	4	70	51	264	290	5
895 + 20 - 898 + 4	US 30 - Ramp	283.3	6	6 & Var	189	216	3		50	36	189	216	4
898 + 4 - 1086 + 13		18809.4	6	10	12540	20899	188	188	3342	2399	12540	20899	48
1086 + 13 - 1089 + 23	Shoulder omission	310	6	10									
1089 + 23 - 1178 + 44		8920.9	6	10	5947	9912	89	89	1585	1138	5947	9912	23
1178 + 44 - 1178 + 77	Approach Shldr Omission	33.4	6	10									
1178 + 77 - 1180 + 39	Steward Cr. Br. Omission	161.7	6	10									
1180 + 39 - 1180 + 90	Approach Shldr Omission	50.7	6	10									
1180 + 90 - 1187 + 50		660	6	10	440	733	7	7	117	84	440	733	3
1187 + 50 - 1187 + 74	Approach Shldr Omission	23.8	6	10									
1187 + 74 - 1189 + 21	BN & SF RR Br. Omission	147.3	6	10									
1189 + 21 - 1189 + 47	Approach Shldr Omission	26.2	6	10									
1189 + 47 - 1193 + 10		362.7	6	10	242	403	4	4	64	46	242	403	2
1193 + 10 - 1193 + 21	Approach Shldr Omission	11.6	6	10									
1193 + 21 - 1194 + 84	Perry Rd Bridge Omission	162.2	6	10									