

SUMMARY OF QUANTITIES

CONSTRUCTION CODE TYPE: MAIN

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	RURAL - 100% STATE	
				US RTE 30	IL RTE 72
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	417	417	
21400100	GRADING AND SHAPING DITCHES	FOOT	14120	9400	4720
25000210	SEEDING, CLASS 2A	ACRE	7.05	4.7	2.35
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	644	432	212
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	644	432	212
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	644	432	212
25100115	MULCH, METHOD 2	ACRE	7.05	4.7	2.35
28000305	TEMPORARY DITCH CHECKS	FOOT	540	340	200
28000400	PERIMETER EROSION BARRIER	FOOT	50	50	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	54		54
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3	3	
50102400	CONCRETE REMOVAL	CU YD	4.8	4.8	
50105200	REMOVE EXISTING CULVERTS	EACH	4		4
50200100	STRUCTURE EXCAVATION	CU YD	25	25	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	300	300	
54002020	EXPANSION BOLTS 3/4 INCH	EACH	12	12	
54003000	CONCRETE BOX CULVERTS	CU YD	2.5	2.5	
54205473	PIPE CULVERTS, CLASS C, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	40		40