

## SCHEDULES OF QUANTITIES

### REMOVAL

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL- BUTT JOINT	PAVEMENT REMOVAL	RETAINING WALL REMOVAL
	SQ YD	SQ YD	FOOT
<b>FAP ROUTE 522 (IL 96)</b>			
STA. 8+47 TO STA. 8+57	33	440	
STA. 8+57 TO STA. 10+00			
STA. 10+00 TO STA. 10+10	33		
RT. STA. 9+54 TO STA. 10+00			46
<b>SOUTH ELM STREET</b>			
RT. STA. 48+77.59 TO STA. 49+70.89			94
<b>LOCAL TRAFFIC DETOUR PLAN</b>			
5TH STREET & LINN STREET	89		
<b>TOTALS</b>			
	155	440	140

### TREE REMOVAL

LOCATION STATION TO STATION	OFFSET FROM E.P.	TREE REMOVAL (OVER 15 UNITS DIAMETER)
	FEET	UNIT
<b>FAP ROUTE 522 (IL 96)</b>		
RT. STA. 8+75	110	38
RT. STA. 8+76	98	36
RT. STA. 8+80	84	24
RT. STA. 8+87	65	20
<b>TOTALS</b>		
		118

### EARTHWORK

LOCATION STATION TO STATION	EARTH EXCAVATION  CU YD	FOR INFORMATION ONLY				REMARKS
		AVERAGE SHRINKAGE FACTOR %	EARTH EXCAVATION (ADJUSTED) CU YD	EMBANKMENT  CU YD	EARTHWORK BALANCE WASTE (+) SHORTAGE (-) CU YD	
<b>FAP ROUTE 522 (IL 96)</b>						
STA. 8+57 TO STA. 10+00	366	73.7	270	399	-129	
<b>NORTH ELM STREET</b>						
STA. 50+15 TO STA. 51+31.46	22	48.1	11	101	-90	
<b>SOUTH ELM STREET</b>						
STA. 48+53.77 TO STA. 49+86.52	580	76.6	444	-	+444	
<b>TOTAL</b>						
	968				+225	

### PERMANENT PAVEMENT MARKINGS

LOCATION STATION TO STATION	EPOXY PAVEMENT MARKING				
	LINE 4"			LINE 6"	LINE 24"
	SOLID WHITE FOOT	SOLID YELLOW FOOT	SKIP DASH FOOT	SOLID WHITE FOOT	SOLID WHITE FOOT
<b>FAP ROUTE 522 (IL 96)</b>					
STA. 8+47 TO STA. 10+10			40		
LT. STA. 8+47 TO STA. 9+09	71				
LT. STA. 9+33 TO STA. 10+10	86				
RT. STA. 8+47 TO STA. 9+38	104				
RT. STA. 9+62 TO STA. 10+10	61				
<b>NORTH ELM STREET</b>					
STA. 50+29 TO STA. 51+31			30		
LT. STA. 50+29					13
LT. STA. 50+30 TO STA. 51+31	101				
RT. STA. 50+29 TO STA. 51+31	102				
STA. 9+08.25 (25.58' LT) TO 9+36.13 (21.21' LT) (IL 96)				54	
<b>SOUTH ELM STREET</b>					
STA. 48+53.77 TO STA. 49+71		235			
LT. STA. 48+53.77 TO STA. 49+64	110				
RT. STA. 48+53.77 TO STA. 49+64	110				
RT. STA. 49+71					14
STA. 9+34.08 (23.60' RT) TO 9+65.91 (23.60' RT) (IL 96)				60	
<b>SUBTOTALS</b>					
	745	235	70	114	27
<b>TOTALS</b>					
		1050		114	27

### ROW MARKERS

LOCATION STATION TO STATION	OFFSET FROM C	FURNISHING AND ERECTING RIGHT OF WAY MARKERS
	FEET	EACH
<b>FAP ROUTE 522 (IL 96)</b>		
RT. STA. 8+73.09	30	1
RT. STA. 8+73.09	100	1
RT. STA. 8+98.09	100	1
RT. STA. 9+48.09	150	1
LT. STA. 9+48.09	70	1
RT. STA. 9+98.09	35	1
LT. STA. 10+28.09	30	1
LT. STA. 10+28.09	70	1
<b>TOTALS</b>		
		8