

TABULATION OF RESURFACING QUANTITIES (CONTINUED)

LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 2 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)		POLYMERIZED LEVELING BINDER (MM), IL-4.75, N50	POLYMERIZED HMA SURFACE COURSE, MIX "D", N50	HMA SHOULDERS		AGGREGATE SHOULDERS, TYPE B		
				COLD-MILLED	FOG COAT	COLD-MILLED	FOG COAT			LEFT	RIGHT	LEFT	RIGHT	
				TON		TON				TON		TON		
WB LANES														
TAZEWELL COUNTY - MAINLINE														
STA. 99 + 17.23	TO STA. 99 + 27.23		48.89	20.00										
STA. 99 + 27.23	TO STA. 101 + 69.02				1,316.43	0.53	0.16	2.20	1.10	46.26	3.36	0.56	0.56	0.19
STA. 101 + 69.02	TO STA. 104 + 03.67				1,029.84	0.41	0.12	1.64	0.82	34.49	68.99	13.54	13.54	4.59
STA. 104 + 3.67	TO STA. 139 + 40.27				15,445.60	6.29	1.89	18.90	9.40	396.10	792.20	473.65	473.65	67.13
STA. 139 + 40.27	TO STA. 142 + 17.49				1,595.99	0.65	0.19	2.25	1.12	47.23	94.46	37.13	284.19	67.13
STA. 142 + 17.49	TO STA. 144 + 24.41				1,368.20	0.52	0.15	2.21	1.10	46.35	92.70	17.97	15.37	5.26
STA. 144 + 24.41	TO STA. 145 + 17.49				534.20	0.20	0.06	0.83	0.42	17.44	34.87	8.09	6.91	3.93
STA. 145 + 17.49	TO STA. 147 + 24.41				1,174.99	0.46	0.14	1.66	0.83	34.76	69.53	28.39	15.37	1.77
STA. 147 + 24.41	TO STA. 148 + 17.49				430.87	0.17	0.05	0.53	0.27	11.23	22.47	12.77	7.82	3.93
STA. 148 + 17.49	TO STA. 208 + 35.67				26,613.89	10.70	3.21	32.10	16.00	674.04	1348.07	825.72	505.52	114.23
STA. 208 + 35.67	TO STA. 211 + 38.89				1,904.15	0.76	0.23	2.74	1.38	57.62	115.23	41.60	25.47	5.76
STA. 211 + 38.89	TO STA. 214 + 37.44				2,148.56	0.84	0.25	3.52	1.76	73.84	147.68	24.12	25.08	5.67
STA. 214 + 37.44	TO STA. 216 + 60.15				1,286.81	0.51	0.15	1.78	0.89	37.42	74.83	31.18	18.71	4.23
STA. 216 + 60.15	TO STA. 222 + 47.19				2,609.13	1.04	0.31	3.13	1.57	65.75	131.50	82.19	49.31	11.14
STA. 222 + 47.19	TO STA. 228 + 38.85				2,206.36	0.85	0.26	3.10	1.55	65.06	130.11	82.83	49.31	11.23
STA. 228 + 38.85	TO STA. 228 + 97.77				144.04	0.06	0.02	0.16	0.08	3.30	6.60	8.25		1.12
STA. 229 + 32.77	TO STA. 258 + 54.72				7,277.53	2.86	0.86	7.79	3.90	163.63	327.26	426.08		55.46
STA. 258 + 54.72	TO STA. 262 + 04.72				1,007.83	0.40	0.12	1.21	0.60	25.32	50.63	51.04		6.64
STA. 262 + 04.72	TO STA. 264 + 12.13				652.89	0.26	0.08	0.83	0.41	17.34	34.68	30.24		3.94
STA. 264 + 12.13	TO STA. 266 + 88.16				810.35	0.41	0.12	1.45	0.72	30.38	60.77	10.95		5.24
STA. 266 + 88.16	TO STA. 269 + 08.78				890.68	0.37	0.11	1.64	0.82	34.49	68.98	8.76		4.19
STA. 269 + 08.78	TO STA. 271 + 13.78				786.70	0.31	0.09	1.11	0.56	23.34	46.69	29.09		3.89
STA. 271 + 13.78	TO STA. 272 + 58.78				403.40	0.16	0.05	0.48	0.24	10.08	20.17	20.58		2.75
STA. 272 + 58.78	TO STA. 365 + 43.41				22,837.39	9.08	2.72	24.80	12.40	519.94	1039.88	1317.69		176.24
STA. 365 + 43.41	TO STA. 371 + 05.45				1,601.00	0.64	0.19	1.94	0.97	40.65	81.31	79.77		10.67
STA. 371 + 05.45	TO STA. 373 + 77.39				709.88	0.37	0.11	1.25	0.62	26.18	52.37	10.90		5.16
STA. 373 + 77.39	TO STA. 375 + 97.41				888.93	0.43	0.13	1.64	0.82	34.40	68.79	8.81		4.18
STA. 375 + 97.41	TO STA. 379 + 47.41				1,184.68	0.38	0.11	1.59	0.80	33.42	66.85	49.00		6.64
STA. 379 + 47.41	TO STA. 425 + 87.37				11,342.15	4.54	1.33	12.40	6.20	259.84	519.68	649.59		88.07
WOODFORD COUNTY - MAINLINE														
STA. 425 + 87.37	TO STA. 453 + 34.17				6,918.27	2.80	0.84	7.64	3.82	160.33	320.67	390.70		54.58
STA. 453 + 34.17	TO STA. 455 + 65.51													
STA. 455 + 65.51	TO STA. 482 + 83.34				6,845.30	2.77	0.83	7.56	3.78	158.64	317.28	386.58		54.03
STA. 482 + 83.34	TO STA. 486 + 33.34				997.89	0.40	0.12	1.21	0.60	25.32	50.63	49.78		6.64
STA. 486 + 33.34	TO STA. 488 + 53.26				712.55	0.28	0.09	0.93	0.46	19.50	39.00	31.28		4.17
STA. 488 + 53.26	TO STA. 491 + 17.85				984.65	0.32	0.10	1.37	0.69	28.81	57.62	37.64		5.02
STA. 491 + 17.85	TO STA. 492 + 17.85				418.08	0.17	0.05	0.74	0.37	15.63	31.27	5.78		1.90
STA. 492 + 17.85	TO STA. 493 + 41.29				437.64	0.21	0.06	0.76	0.38	16.00	32.01	7.13		2.34
STA. 493 + 41.29	TO STA. 494 + 47.85				346.60	0.15	0.05	0.52	0.26	10.83	21.66	11.18		2.02
STA. 494 + 47.85	TO STA. 497 + 97.85				894.25	0.40	0.12	1.21	0.60	25.32	50.63	36.72		6.64
STA. 497 + 97.85	TO STA. 515 + 37.50BK				4,293.13	1.63	0.49	5.75	2.88	120.78	241.55	178.60		50.66
STA. 315 + 00.00AH	TO STA. 316 + 97.45	17.78	8.89		821.35	0.33	0.10	1.59	0.79	33.35	66.70	3.44		9.37

FILE NAME = 68467 - Phase II.dgn	USER NAME = j.gibson	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SHEET NO. 2 OF 7 SHEETS

Rev. Sheet 2-11-10

F.A.P. RTE. 317	SECTION 17RS-6; 18RS-1; 35RS-8	COUNTY TAZEWELL WOODFORD	TOTAL SHEETS 60	SHEET NO. 20
CONTRACT NO. 68467			ILLINOIS FED. AID PROJECT	