



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 17, 2010

SUBJECT: FAS Route 411 (IL 164)
Section 103RS; (1,3)RS3
Warren County
Contract No. 68605
Item No. 92, March 5, 2010 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page i of the Table of Contents to the Special Provisions.
2. Added page 53 to the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Joseph E. Crowe, Region 3, District 4; Mike Renner; Estimates

TBW:DB:jc

TABLE OF CONTENTS

LOCATION OF PROJECT 1

DESCRIPTION OF PROJECT 1

PLACEMENT OF HOT-MIX ASPHALT SURFACE COURSES 1

HOT-MIX ASPHALT SURFACE COURSE SURFACE TESTS 1

MATERIAL TRANSFER DEVICE (BDE) 2

RUMBLE STRIP 3

HOT-MIX ASPHALT SURFACE REMOVAL, ½" (20 MM) 3

TRAFFIC CONTROL PLAN 6

APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE) 6

AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE) 6

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) 8

CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE) 9

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 10

EQUIPMENT RENTAL RATES (BDE) 18

FLAGGER AT SIDE ROADS AND ENTRANCES (BDE) 19

HOT-MIX ASPHALT – ANTI-STRIPPING ADDITIVE (BDE) 19

HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE) 20

HOT-MIX ASPHALT – DROP-OFFS (BDE) 21

HOT-MIX ASPHALT – PLANT TEST FREQUENCY (BDE) 21

HOT-MIX ASPHALT – QC/QA ACCEPTANCE CRITERIA (BDE) 22

HOT-MIX ASPHALT – TRANSPORTATION (BDE) 22

LIQUIDATED DAMAGES (BDE) 23

MONTHLY EMPLOYMENT REPORT (BDE) 23

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) 24

PAVEMENT PATCHING (BDE) 26

PAYMENTS TO SUBCONTRACTORS (BDE) 26

PERSONAL PROTECTIVE EQUIPMENT (BDE) 27

RAISED REFLECTIVE PAVEMENT MARKERS (BDE) 27

RECLAIMED ASPHALT PAVEMENT (RAP) (BDE) 27

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) 34

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 35

WORKING DAYS (BDE) 35

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) (RETURN FORM WITH BID) 36

PROJECT LABOR AGREEMENT 39

AGGREGATE QUALITY 53

AGGREGATE QUALITY

Effective July 1, 1990

Revised September 23, 1996

Coarse aggregate for Granular Embankment Special, Sub-base Granular Material, Aggregate Shoulders, Aggregate Surface and Base Courses, and Erosion Control Aggregate shall conform to Article 1004.04 of the Standard Specifications for Road and Bridge Construction except that all of the following revisions to Article 1004.04(b) shall apply:

1. Revise the maximum allowable percentage of weighted average loss when the material is subjected to 5 cycles of sodium sulfate soundness test from 25%, as shown under the Class D of the Quality Chart in Article 1004.01(b) of the Standard Specifications, to 40%; and
2. Revise the maximum allowable percentage of wear as determined by the Los Angeles Abrasion Method from 45%, as shown under Class D of the Quality Chart in Article 1004.01(b) of the Standard Specifications, to 65%; and
3. The sum of the percentages of weighted average loss when the material is subjected to 5 cycles of the sodium sulfate soundness test and the percentage of wear as determined by the Los Angeles Abrasion Method shall not exceed 95%.

Added 02/17/2010