

JOB SPECIFIC NOTES

Traffic Barrier Terminal, Type 1 Special (Tangent) When attached to existing guardrail

Road System, Inc
 3616 Old Howard County Airport
 Big Spring, TX 79720
 Phone: 915-263-2435
 "SKT"

Wood blockouts only. Wood post system Only. Post 1 & 2 to use steel soil tubes (6'-6" or 6'-0" with wood post). Post 3 through 8 to use 4'-6" soil tubes with wood posts (soil plates not required), OR post 3 through 8 may be 6' CRT posts.

Trinity Industries, Inc.
 2525 N. Stemmons Freeway
 Dallas, TX 75207
 Phone: 800-644-7976 or 801-292-4461
 "ET-2000"

Wood blockouts only. A wood system may be used. Post 1 & 2 to use steel soil tubes (6'-6" or 6'-0" with wood posts). Posts 3 through 8 to use 4'-6" soil tubes with wood posts (soil plates not required), OR posts 3 through 8 may be 6' CRT posts. OR a system using the Steel Yielding Terminal Post (SYTP) (Posts 2 to 8) and one Hinged Break Away Post (HBA) (Post 1) may be used.

Sideroads

Milling and Resurfacing limits need to be verified by the Resident Engineer prior to each operation.

Permanent Survey Markers

Contractor shall notify the Resident Engineer two weeks prior to any bituminous surface removal to allow sufficient time to locate existing survey markers.

Guardrail Aggregate Erosion Control

Excavation for the placement of Guardrail Aggregate Erosion control will not be paid for separately, but shall be included in the cost of Guardrail Aggregate Erosion Control pay item.

FILE NAME = D468747-sht-planudgn	USER NAME = mendezpj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	JOB SPECIFIC NOTES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			643	(11,12)RS-2;(6)WRS-3;(10)RS-4	STARK	45	4
	PLOT DATE = 12/7/2009	DATE -	REVISED -			CONTRACT NO. 68747		ILLINOIS FED. AID PROJECT		
					SCALE: NONE	SHEET NO.	OF	SHEETS	STA.	TO STA.