SHORT-TERM PAVEMENT MARKING

LOCATION STATION	LENGTH FOOT	70300100 FOOT
IL 17/91		
STA 00+39 TO STA 151+15.45	15,076.45	4,523
STA EQ 151+15.45 = 135+35.35		
STA 135+35.35 TO STA 220+84.30	8,548.95	2,565
STA EQ 220+84.30 = 204+98.10		
STA 204+98.10 TO STA 285+75	8,076.90	2,423
IL 17		
STA 99+54 TO STA 103+78	424.00	127
STA EQ 103+78 = 00+00		
STA 00+00 TO STA 346+24	34,624.00	10,387
TOTAL		20,025

*** Note: 3 Applications**

WORK ZONE PAVEMENT MARKING REMOVAL

LOCATION	70301000 SQ FT
IL 17/91	1,057
IL 17	1,172
TOTAL	**2,229**

EPOXY PAVEMENT MARKING - LETTER AND SYMBOLS

LOCATION	LT/RT	LEFT TURN ARROW SQ FT	RIGHT TURN ARROW SQ FT
IL 17			
STA 341+04.88		15.6	
STA 341+74.81		15.6	
STA 343+63.65	LT		15.6
STA 344+63.65	LT		15.6
SUB - TOTAL		31.2	31.2
TOTAL			62.4

TEMPORARY PAVEMENT MARKING - LETTER AND SYMBOLS

LOCATION	LT/RT	LEFT TURN ARROW SQ FT	RIGHT TURN ARROW SQ FT
IL 17			
STA 341+04.88		15.6	
STA 341+74.81		15.6	
STA 343+63.65	LT		15.6
STA 344+63.65	LT		15.6
SUB - TOTAL		31.2	31.2
TOTAL			62.4

EPOXY PAVEMENT MARKING - LINE 12"

LOCATION STATION TO STATION	YELLOW DIAGONAL FOOT	WHITE DIAGONAL FOOT
IL 17		
STA 336+20 TO STA 341+00	131	
LT STA 341+85.5 TO STA 342+29.17		92
LT STA 342+57.3 TO STA 343+35.2		129
STA 342+78.32 TO STA 346+68.58	152	
SUB TOTAL	282	222
TOTAL		504

TEMPORARY PAVEMENT MARKING - LINE 12"

LOCATION STATION TO STATION	YELLOW DIAGONAL FOOT	WHITE DIAGONAL FOOT
IL 17		
STA 336+20 TO STA 341+00	131	
LT STA 341+85.5 TO STA 342+29.17		92
LT STA 342+57.3 TO STA 343+35.2		129
STA 342+78.32 TO STA 346+68.58	152	
SUB TOTAL	282	222
TOTAL		504

EPOXY PAVEMENT MARKING - LINE 24"

LOCATION STATION TO STATION	STOP BAR FOOT
IL 17	
STA 342+00	13
LT STA 342+28 TO STA 342+42	14
TOTAL	27

TEMPORARY PAVEMENT MARKING - LINE 24"

LOCATION STATION TO STATION	STOP BAR FOOT
IL 17	
STA 342+00	13
LT STA 342+28 TO STA 342+42	14
TOTAL	27

ENGINEER'S FIELD OFFICE, TYPE A

LOCATION	67000400 CAL MO
JOBSITE	4
TOTAL	4