



Typical Section
 IL Route 6
 Northbound
 Sta. 167+33 to 168+33
 Sta. 169+71 to Sta. 170+71
 Sta. 213+63 to 214+62
 Sta. 216+26 to 217+68
 Sta. 219+29 to 220+30

Southbound
 Sta. 167+39 to 168+39
 Sta. 169+65 to 170+65
 Sta. 213+32 to 214+56
 Sta. 216+32 to 217+65
 Sta. 219+32 to 220+34

LEGEND

1. Existing PCC Pavement
2. Existing Hot-Mix Asphalt Overlay
3. Existing BAM Shoulder with Hot-Mix Asphalt Overlay
10. Proposed Hot-Mix Asphalt Surface Removal 2"
11. Proposed Hot-Mix Asphalt Surface Removal 4 1/4"
12. Proposed Hot-Mix Asphalt Surface Course, Mix "E", N90 2"
13. Proposed Hot-Mix Asphalt Shoulders 4 1/4"
14. Proposed Hot-Mix Asphalt Shoulders 2", Mix "C", N50
15. Proposed Preformed Plastic Pavement Marking, Type B-Inlaid, 6"
16. Proposed Urethane Pavement Marking, 4"
17. Proposed Hot Mix Asphalt Removal (Deck)
18. Proposed Water Proofing Membrane System
19. Proposed Hot-Mix Asphalt Removal Complete
20. Proposed Aggregate Shoulders, Type B

Note:
 HOT-MIX ASPHALT SURFACE REMOVAL 2" on the shoulders shall be done in accordance with Article 440 of the Standard Specifications.

* At shoulder locations constructed of PCC, this area will be measured and paid for as HOT-MIX ASPHALT SURFACE REMOVAL, 2".

**Match existing slope for HOT-MIX ASPHALT SURFACE REMOVAL, 2".

FILE NAME = 174.dgn	USER NAME = everacl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS			F.A.P. RTE. 318	SECTION 72-(17)RS-2(1,7-11)	COUNTY PEORIA	TOTAL SHEETS 30	SHEET NO. 6
	PLOT SCALE = 400.0000' / IN.	DRAWN -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 68847				
	PLOT DATE = 12/14/2009	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -									