



Typical Section
Structure Locations

- Northbound
 *Sta. 168+33 to 169+71-SN 072-0138
 Sta. 214+62 to 216+26-SN 072-0107
 Sta. 217+68 to 219+29-SN 072-0109
- Southbound
 *Sta. 168+39 to 169+65-SN 072-0139
 Sta. 214+56 to 216+32-SN 072-0106
 Sta. 217+65 to 219+32-SN 072-0108
 Sta. 511+56 to 514+55 - SN 072-0111

LEGEND

1. Existing PCC Pavement
2. Existing Hot-Mix Asphalt Overlay
3. Existing BAM Shoulder with Hot-Mix Asphalt Overlay
10. Proposed Hot-Mix Asphalt Surface Removal 2"
11. Proposed Hot-Mix Asphalt Surface Removal 4 1/4"
12. Proposed Hot-Mix Asphalt Surface Course, Mix "E", N90 2"
13. Proposed Hot-Mix Asphalt Shoulders 4 1/4"
14. Proposed Hot-Mix Asphalt Shoulders 2", Mix "C", N50
15. Proposed Preformed Plastic Pavement Marking, Type B-Inlaid, 6"
16. Proposed Urethane Pavement Marking, 4"
17. Proposed Hot Mix Asphalt Removal (Deck)
18. Proposed Water Proofing Membrane System
19. Proposed Hot-Mix Asphalt Removal Complete
20. Proposed Aggregate Shoulders, Type B

Note:
 HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N90 depth at the structures shall match existing expansion joint grades (nominal 1 1/2").

*HOT-MIX ASPHALT SURFACE REMOVAL COMPLETE and WATERPROOFING MEMBRANE SYSTEM will be done on structures 072-0138 & 072-0139.

FILE NAME = 174.dgn	USER NAME = everocl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS	F.A.R. RTE. 318	SECTION 72-(17)RS-2(1,7-11)	COUNTY PEORIA	TOTAL SHEETS 30	SHEET NO. 7		
	PLOT SCALE = 400.0000' / IN.	DRAWN -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		CONTRACT NO. 68847				
	PLOT DATE = 12/10/2009	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT						
		DATE -	REVISED -									