

SCHEDULE OF GUARDRAIL QUANTITIES

LOCATION	GUARDRAIL REMOVAL**	STEEL PLATE BEAM GUARDRAIL, TY A, 6' POSTS	TRAFFIC BARRIER TERMINAL REMOVAL, TY 1	TRAFFIC BARRIER TERMINAL TY 1, SPECIAL (TANGENT)	GUARDRAIL MARKERS, TYPE A	TERMINAL MARKER - DIRECT APPLIED	GUARDRAIL AGG. EROSION CONTROL	VERTICAL ADJUSTMENT OF GUARDRAIL
	FOOT	FOOT	EACH	EACH	EACH	EACH	TON	FT
IL 17								
MARSHALL COUNTY								
LT. STA. 66+16.29 TO STA. 75+78.79			2	2		2	10.13	
RT. STA. 66+16.29 TO STA. 75+78.79	50	50	2	2	2	2	15.20	
LT. STA. 76+28.59 TO STA. 78+91.09			2	2		2	10.13	
LT. STA. 95+80.29 TO STA. 101+42.79			2	2		2	10.13	
RT. STA. 95+80.29 TO STA. 101+42.79	37.5	37.5	2	2	1	2	13.93	
LT. STA. 117+95.89 TO STA. 121+33.39			2	2		2	10.13	
RT. STA. 117+95.89 TO STA. 120+33.39			2	2		2	10.13	
LT. STA. 329+18.39 TO STA. 331+05.89			2	2		2	10.13	
RT. STA. 328+78.39 TO STA. 330+65.89			1	1		1	5.07	
LT. STA. 380+26.89 TO STA. 382+01.89			2	2		2	10.13	
RT. STA. 380+38.89 TO STA. 407+13.89	37.5	37.5	2	2	1	2	13.93	
IL 89								
PUTNAM COUNTY								
LT. STA. 570+88.95 TO STA. 574+38.95			2	2		2	10.13	
LT. STA. 580+76.95 TO STA. 578+76.95			2	2		2	10.13	
RT. STA. 579+39.95 TO STA. 576+27.45			2	2		2	10.13	
LT. STA. 606+30.00 TO STA. 603+67.50			2	2		2	10.13	
RT. STA. 604+84.00 TO STA. 603+71.50			2	2		2	10.13	
MARSHALL COUNTY								
LT. STA. 627+12.00 TO STA. 623+62.00			2	2		2	10.13	
RT. STA. 626+44.00 TO STA. 630+94.00			2	2		2	10.13	
LT. STA. 637+92.00 TO STA. 641+17.00			2	2		2	10.13	
RT. STA. 638+63.00 TO STA. 641+13.00			2	2		2	16.47	62.50
LT. STA. 666+62.96 TO STA. 670+97.10			2	2		2	10.13	
RT. STA. 666+62.96 TO STA. 670+97.10			2	2		2	10.13	
LT. STA. 703+92.00 TO STA. 699+04.50			2	2		2	10.13	
RT. STA. 703+04.00 TO STA. 698+04.00			2	2		2	10.13	
LT. STA. 753+43.00 TO STA. 748+30.50								
RT. STA. 754+20.00 TO STA. 749+07.50								
LT. STA. 782+90.00 TO STA. 774+52.50			2	2		2	10.13	
RT. STA. 783+36.00 TO STA. 774+86.00			2	2		2	22.80	125.00
RT. STA. 844+82.00 TO STA. 840+94.50			2	2		2	10.13	
RT. STA. 854+80.00 TO STA. 852+67.50			2	2		2	10.13	
SUB-TOTAL:	125.0	125.0	55	55	4	55	310.33	187.5
TOTAL:	125	125	55	55	4	55	310	188

NOTE: STATIONS ARE APPROXIMATE
 ** REMOVAL OF DAMAGED GUARDRAIL