

SCHEDULE OF QUANTITIES

EARTH EXCAVATION (WIDENING)

LOCATION	CUYD
Sta.155+86 Lt.13' to 158+82 Lt. 13'	16.6
Sta.156+36 Rt.13' to 158+82 Rt. 13'	13.8
Sta.159+62 Lt.13' to 162+00 Lt. 13'	13.3
Sta.159+62 Rt.13' to 162+00 Rt. 13'	13.3
TOTAL	57

BASE COURSE WIDENING, 9"

LOCATION	SQYD
Sta.155+86 Lt.13' to 158+82 Lt. 13'	65.8
Sta.156+36 Rt.13' to 158+82 Rt. 13'	54.8
Sta.159+62 Lt.13' to 162+00 Lt. 13'	53.2
Sta.159+62 Rt.13' to 162+00 Rt. 13'	53.2
TOTAL	227

HMA SURFACE COURSE MIX "D", N50

LOCATION	TON
Bridge Approach Transitions	15
TOTAL	15

POLY. BIT. MAT. PRIME COAT

LOCATION	GAL
Bridge Approach Transitions	22
TOTAL	22

PROTECTIVE COAT

LOCATION	SQYD
N. Joint, Parapet, Latex Overlay & S. Stop-Block	327
TOTAL	327

HMA SURFACE REMOVAL DECK

LOCATION	SQYD
Jobsite - SN.102-0041	261
TOTAL	261

CONCRETE REMOVAL

LOCATION	CUYD
North Joint & Parapets	13.5
TOTAL	13.5

CONCRETE SUPERSTRUCTURE

LOCATION	CUYD
North Joint & Parapets	13.6
TOTAL	13.6

BRIDGE DECK GROOVING

LOCATION	SQYD
Jobsite - SN.102-0041	258
TOTAL	258

TEMPORARY RAMP

LOCATION	SQYD
Bridge Approach Transitions	36
TOTAL	36

HMA SURFACE COURSE REMOVAL, 1 1/2"

LOCATION	SQYD
Bridge Approach Transitions	178
TOTAL	178

STRUCTURAL REPAIR OF CONCRETE

LOCATION	SQFT
NE Backwall Corners	8.9
NW Backwall Corners	9.1
TOTAL	18

REINFORCEMENT BARS, EPOXY COATED

LOCATION	POUND
N. Joint, Parapet	1480
TOTAL	1480

BAR SPLICERS

LOCATION	EACH
North Joint	17
TOTAL	17

REMOVING & RE-ERECTING EXISTING RAILING

LOCATION	FOOT
Parapets	88
TOTAL	88

MOBILIZATION

LOCATION	LSUM
Jobsite - SN.102-0041	1
TOTAL	1

T C & P. STANDARD 701321

LOCATION	EACH
Jobsite - SN.102-0041	1
TOTAL	1

T. C. & P STANDARD 701201

LOCATION	LSUM
Jobsite - SN.102-0041	1
TOTAL	1

TEMPORARY BRIDGE TRAFFIC SIGNALS

LOCATION	EACH
Jobsite - SN.102-0041	1
TOTAL	1

TEMPORARY RUMBLE STRIP

LOCATION	EACH
Jobsite - SN.102-0041	14
TOTAL	14

CHANGEABLE MESSAGE SIGN

LOCATION	CALMO
Jobsite - SN.102-0041	6
TOTAL	6

S:\GEN\DRFT\1510\PLUS\504041\BRIDGE CONTRACTS\JOINTS\JOINTS\JOINTS - Diver\eg\AB9128 SN.102-0041\IL.117\ovr\MILL CRK.dgn

SN. 102-0041 IL.117 ovr
MILL CRK. S. of US24

FILE NAME =	USER NAME = *USER*	DESIGNED - CEJ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES	F.A.P. RTE. 702	SECTION (14BR-1)I	COUNTY WOODFORD	TOTAL SHEETS 23	SHEET NO. 4
#FILE#		DRAWN - CEJ	REVISED -			MISC. BRIDGE REPAIRS				CONTRACT NO. 68928
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -		SCALE:	SHEET NO. OF SHEETS	STA.	TO STA.		FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT
	PLOT DATE = *DATE*	DATE - 09/03/2009	REVISED -							